

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05251104 Call Order: 006 Proposal: E59D3-R0 District:05
 Counties: LAKE, ORANGE

Road Name: MISCELLANEOUS CONCRETE REPAIR
 Limits: Midpoint

Project(s): 42795617269(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	11/04/25
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

Description:

FDOT District 5
 Proposal ID No.: E59D3
 Financial Project No.: 427956-1-72-69
 Fiscal Year: 2026
 Counties: Lake and Orange
 Calendar Days: 365

This is a Maintenance Work Document driven Contract with a budget estimate of \$400,000.00. The Contract will be awarded at the budget estimate amount. This Contract includes an option for renewal(s).

Intent:

The work under this Contract consists of performing miscellaneous concrete repairs, including sidewalks, inlet tops, curb and gutter, mitered end sections, and concrete slope pavement on an as-needed basis within Department rights-of-way, easements, and parcels located in Lake County and a small portion of Orange County.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of concrete repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Portland Cement Concrete Roadway Paving" will suffice to meet the above requirements.

Note:

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 006 Proposal: E59D3-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CONCRETE REPAIR (CY)				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,200.000
	0120- 6-	EMBANKMENT	CY	10.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	1.000
	0425- 15- 42	INLET TOP, REPAIR, DITCH BOTTOM INLET	EA	10.000
	0425- 15- 51	INLET TOP, REPLACE, CURB INLET	EA	8.000

Call Order: 006 Proposal: E59D3-R0

ALT	Item	Description	Unit	Quantity
	0425- 15- 52	INLET TOP, REPLACE, DITCH BOTTOM INLET	EA	1.000
	0425- 16- 11	DRAINAGE MANHOLE- REPLACE TOP AND RIM	EA	10.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-602-125	U-ENDWALL, WITH GRATE, INDEX 260/430-010, 1:4 SLOPE, 18"	EA	1.000
	0430-602-129	U-ENDWALL, WITH GRATE, INDEX 260/430-010, 1:4 SLOPE, 24"	EA	1.000
	0430-602-133	U-ENDWALL, WITH GRATE, INDEX 260/430-010, 1:4 SLOPE, 30"	EA	1.000
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	5.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	25.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	12.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	5.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	5.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	1.000
	0430-984-121	MITERED END SECTION, OPTIONAL ROUND, 12" SD	EA	1.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	3.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	1.000
	0430-984-140	MITERED END SECTION , OPTIONAL ROUND, 42" SD	EA	1.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	5.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	100.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	250.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	100.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	125.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,000.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	200.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	20.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	20.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	20.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	20.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	20.000
	0527- 2-	DETECTABLE WARNINGS	SF	20.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	5.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	250.000
	0920-530-100	FABRIC FORMED CONCRETE RIPRAP	SY	100.000
	E110- 2-	CLEARING & GRUBBING	AC	0.500
	E524- 1- 1	CONCRETE DITCH PAVEMENT REPAIR	CY	25.000
	E524- 2- 1	CONCRETE SLOPE PAVEMENT REPAIR	CY	15.000