Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 05251007 Call Order: 002 Proposal: E59F7 District:05

Counties: LAKE

Road Name: Lake County Signalization Pushbutton Contract with MOB

Limits: Midpoint

Project(s): 44081665201(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 730

Total Bridge Length: 0.000 Miles Letting Date: 10/07/25

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time:

Proposal Budget Estimate: \$2,000,000.00

Please read the full advertisement

Description:

The intent of this contract is to provide means for the DEPARTMENT to quickly respond to traffic operations safety and/or operational issues for a period of two (2) years or until the contracted amount has been reached.

The Improvements under this Contract consist of installing new, repairing and/or modifying traffic signalization infrastructure, signing and pavement markings, pedestrian signal installations, such as, crosswalks, accessible pedestrian signals, and midblock crosswalks. All of the improvements under this contract will remain within the Lake County boundary.

The Contractor shall furnish all labor, materials, equipment, tools, transportation, and supplies required to complete the work in accordance with the work plan, specifications, procedures, and terms of the contract. The DEPARTMENT will not specify contractor crew size, work methods or equipment complements, provided the desired work quality is achieved as evaluated by the Project Engineer. The work under this Contract will be controlled by the issuance of Work Documents. All work in this contract is considered specialty work. The number of work documents for the contract will be limited by a budgetary cap of \$2,000,000.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

PREQUALIFICATION REQUIRED

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1- 1	MOBILIZATION- FOR WORK ORDER/PUSH BUTTON CONTRACTS (DO NOT BID) (44081665201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	150.000
	0102- 60-	WORK ZONE SIGN	ED	2,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	50.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	120.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	120.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	50.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	50.000

		Call Order: 002 Proposal: E59F7		
ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	1.000
	0110- 4-10	REMOVAL OF EXISTING CONCRETE	SY	120.000
	0120- 1-	REGULAR EXCAVATION	CY	40.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	20.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	40.000
	0334- 1-13 0337- 7-83	SUPERPAVE ASPHALTIC CONC, TRAFFIC C ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22	TN TN	7.000 4.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	20.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	50.000
	0520- 1-10	CONCRETE CURB & GUTTER, TYPE F	LF	350.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	150.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	50.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	50.000
	0527- 2-	DETECTABLE WARNINGS	SF	100.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	250.000
ection	n 0002 Signing			
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 5-22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	5.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	50.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	720.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,000.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	467.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	100.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	200.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.000

		Call Order: 002 Troposal: E3317		
ALT	Item	Description	Unit	Quantity
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	1,000.000
	0715- 1-11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR < (k)	LF	100.000
	0715- 1-12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,698.000
	0715- 7-11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 61-211	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	1.000
	0715- 66-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH (k)	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	4.000
Sectio	n 0003 Signalizat	tion		
	0630- 2-11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,000.000
	0630- 2-12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,000.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	600.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,000.000
	0633- 2-31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	10.000
	0633- 2-32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	5.000
	0633- 3-12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	2.000
	0633- 3-13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	4.000
	0633- 3-15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	1.000
	0633- 3-16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 3-17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	1.000
	0633- 8-11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	50.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	2.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	2.000
	0634- 5- 1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	20.000
	0635- 2-11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	52.000
	0635- 2-12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	6.000
	0635- 2-13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	3.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	500.000
	0639- 3-11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0641- 2-12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	6.000
	0641- 2-18	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VIII	EA	12.000
	0646- 1-11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000

ALT	Item	Description	Unit	Quantity
	0650- 1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	14.000
	0650- 1-16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0653- 1-11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	7.000
	0653- 1-12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	11.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	13.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	12.000
	0660- 3-11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 3-12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	16.000
	0660- 4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	4.000
	0660- 4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	16.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	1.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	3.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1.000
	0665- 1-11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	32.000
	0670- 5-162	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 2 PREEMPTION	AS	3.000
	0670- 5-300	TRAFFIC CONTROLLER ASSEMBLY, INSTALL	AS	1.000
	0671- 2-40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0684- 6- 1	WIRELESS COMMUNICATION SYSTEM DEVICE, FURNISH & INSTALL	EA	2.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	1.000
	0685- 1-13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	3.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	3.000