

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05250903	Call Order: 008	Proposal: E58F2	District:05
Counties:	SUMTER			
Road Name:	SR 48			
Limits:	18060000			
Project(s):	45063515201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.258 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	09/03/25	
Total Proposal Length:	0.258 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	

Proposal Budget Estimate: \$759,769.00

Please read the full advertisement

Description:

SR 48/SR 475 FROM BELT AVENUE TO NOBLE AVENUE - PAVEMENT ONLY RESURFACE (FLEX)

The Improvements under this Contract consist of milling and resurfacing, driveway improvements, sidewalk improvements (including detectable warnings), and signing and pavement markings on SR 48/SR 475 (N. Main St.) from Belt Avenue to Noble Avenue, approximately 0.258 miles in Sumter County.

Railroad insurance required.

PREQUALIFICATION REQUIRED

Call Order: 008 Proposal: E58F2

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45063515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45063515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	3,807.000
	0102- 61-	BUSINESS SIGN	EA	3.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,086.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	851.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	126.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	228.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	200.000
	0104- 10- 3	SEDIMENT BARRIER	LF	130.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0107- 1-	LITTER REMOVAL	AC	3.230
	0107- 2-	MOWING	AC	0.490
	0110- 1- 1	CLEARING & GRUBBING (45063515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	96.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	26.300
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45063515201)	LS	1.000

Call Order: 008 Proposal: E58F2

ALT	Item	Description	Unit	Quantity
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	9,152.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,838.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	755.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	906.600
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	82.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	26.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	71.000
	0527- 2-	DETECTABLE WARNINGS	SF	57.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	24.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.458
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	131.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	161.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.409
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.473
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	44.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45063515201)	LS	1.000
Section 0002 Signing				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	100.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	11.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	13.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	189.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45063515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	911.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	188.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	58.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	622.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.517
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.415

Call Order: 008 Proposal: E58F2

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.532
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	523.000