

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05250903	Call Order: 009	Proposal: E58F3	District:05
Counties:	SUMTER			
Road Name:	SR 50/SR 471			
Limits:	18020000			
Project(s):	45077215201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.915 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	09/03/25	
Total Proposal Length:	0.915 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 FLEX	

Proposal Budget Estimate: \$709,044.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing and loop replacements for the included traffic monitoring site and existing signal on State Road 50/SR 471 from west of County Road 739 to east of State Road 471 (Tarrytown), approximately 0.915 miles in Sumter County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at: <https://www.fdot.gov/equalopportunity/bdi.shtm>.

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year. Send a completed and notarized affidavit as an attachment to: SmallBusiness@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the projects major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://pdl.fdot.gov>.

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

Call Order: 009 Proposal: E58F3

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45077215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45077215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	156.000
	0102- 60-	WORK ZONE SIGN	ED	3,360.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,760.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	216.000

Call Order: 009 Proposal: E58F3

ALT	Item	Description	Unit	Quantity
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	536.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	120.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	120.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	240.000
	0107- 1-	LITTER REMOVAL	AC	31.940
	0107- 2-	MOWING	AC	28.560
	0110- 1- 1	CLEARING & GRUBBING (45077215201)	LS	1.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	19,378.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,598.700
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,988.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	40.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	350.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.886
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	586.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	96.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	657.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.072
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	7.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.621
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.692
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45077215201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	1.770
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	205.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45077215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	587.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	96.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	115.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	60.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	508.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.881

Call Order: 009 Proposal: E58F3

ALT	Item	Description	Unit	Quantity
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.074
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.619
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.692
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	36.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000