

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05260407	Call Order: 002	Proposal: E50G9	District:05
Counties:	MARION			
Road Name:	SR 500			
Limits:	36220000			
Project(s):	45063715201(*)	Federal Aid No:	N/A	
Project(s):	45063725201	Federal Aid No:	N/A	
Total Roadway Length:	8.169 Miles	Contract Days:	260	
Total Bridge Length:	0.033 Miles	Letting Date:	04/07/26	
Total Proposal Length:	8.202 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 FLEX	
Proposal Budget Estimate:	\$10,184,153.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, reconstruction, signing and pavement markings, and signalization loop replacement on State Road 500 (US 27/441) from north of SE 178th Place to south of SE 62nd Avenue, approximately 8.202 miles in Marion County.

PREQUALIFICATION REQUIRED

Call Order: 002 Proposal: E50G9

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45063715201)	LS	1.000
	0101- 1-	MOBILIZATION (45063725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45063715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45063725201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,852.000
	0102- 60-	WORK ZONE SIGN	ED	21,060.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	88,400.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,040.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,644.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,820.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,820.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,040.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,040.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,210.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	53.000
	0107- 1-	LITTER REMOVAL	AC	1,113.810
	0107- 2-	MOWING	AC	1,031.500
	0110- 1- 1	CLEARING & GRUBBING (45063715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45063725201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,062.800
	0120- 6-	EMBANKMENT	CY	1,075.000

Call Order: 002 Proposal: E50G9

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	5,790.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,159.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,123.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	279,328.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	74,972.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	340.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	37,472.600
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	163.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	45,825.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	224.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	335.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	208.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-PEDESTAL/SERVICE POLE	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	3.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,211.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.369
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	22.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.093
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	11.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.089
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.161
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45063725201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	16.123
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	325.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	36.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	19.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	208.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	88.000

Call Order: 002 Proposal: E50G9

ALT	Item	Description	Unit	Quantity
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	10.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	36.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	239.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,670.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	2,136.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45063715201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45063725201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,407.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	2,475.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.562
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	430.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	90.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,223.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.861
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	6.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	6.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	19.202
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.426
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	15.897
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	14.180
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.066
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.066
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.066
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.066
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	522.000