

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 05260407      Call Order: 009      Proposal: E56D7      District:05  
Counties: VOLUSIA

Road Name: Drainage Repair  
Limits: Midpoint

Project(s): 41232657258(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	150
Total Bridge Length:	0.000 Miles	Letting Date:	04/07/26
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	07/01/26
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$425,000.00

Please read the full advertisement

**Description:**

FDOT District 5  
Proposal ID No.: E56D7  
Financial Project No.: 412326-5-72-58  
Fiscal Year: 2026  
County: Volusia  
Contract Calendar Days: 150  
Lead Time: 14 Days

This is a Maintenance Pay Item Contract. Contract Time begins on July 1, 2026.

**Intent:**

The work under this Contract consists of drainage system restoration, including ditch cleaning; culvert, inlet and side drain replacement; and concrete ditch pavement installation.

**Experience:**

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 009 Proposal: E56D7**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ROADSIDE DITCHES-CLEAN AND RESHAPE (LF)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	688.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	94.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	0.500
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	935.800
	0120- 6-	EMBANKMENT	CY	18.100
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	159.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	223.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	4.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	4.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	426.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,977.000