Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05260303 Call Order: 004 Proposal: E53E2 District:05

Counties: BREVARD

Road Name: Asphalt Repair

Limits: Midpoint

Project(s): 42914217232(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	45
Total Bridge Length:	0.000 Miles	Letting Date:	03/03/26
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: $3,000,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID No.: E53E2
Financial Project No: 429142-1-72-32
Fiscal Year: 2026
County: Brevard
Calendar Days: 45
Lead Time: 14 Days

This is a Maintenance Pay Item Contract.

Intent:

The work under this Contract consists of FC-5 asphalt repairs at various locations on Interstate 95 in Brevard County. The work includes milling an average 1" of asphalt surface, installation of 1” of FC-5, and minor pavement marking restoration.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Asphalt Paving projects, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course" will suffice to meet the above requirements.

Call Order: 004 Proposal: E53E2

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	88,054.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,711.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	13.647
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,585.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	4.101
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.002
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.892