

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05261103	Call Order: 002	Proposal: E53G0	District:05
Counties:	MARION			
Road Name:	SR 25			
Limits:	36030000			
Project(s):	45263515201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.284 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	11/03/26	
Total Proposal Length:	0.284 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120	
Proposal Budget Estimate:	\$1,026,187.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Milling & Resurfacing, Curb & Gutter, Sidewalk, Traffic Signals, and Signing/Pavement Markings on State Road 25/200 (US 27 / US 301 / US 441) from SW 10th St to SW 4th St approximately 0.284 miles in Marion County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at: <https://www.fdot.gov/equalopportunity/bdi.shtm>.

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents.

The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year. Send a completed and notarized affidavit as an attachment to: SmallBusiness@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the projects major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://pdl.fdot.gov>.

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

Call Order: 002 Proposal: E53G0

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45263515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45263515201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45263515201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	240.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	112.000
	0102- 60-	WORK ZONE SIGN	ED	4,617.000

Call Order: 002 Proposal: E53G0

ALT	Item	Description	Unit	Quantity
	0102- 61-	BUSINESS SIGN	EA	8.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,466.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	52,749.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	179.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	586.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	408.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-115-	TYPE III BARRICADE	ED	88.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0107- 1-	LITTER REMOVAL	AC	5.210
	0107- 2-	MOWING	AC	2.300
	0110- 1- 1	CLEARING & GRUBBING (45263515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	284.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	3,579.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,275.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	3,583.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	787.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,108.500
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	286.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	78.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	166.000
	0527- 2-	DETECTABLE WARNINGS	SF	474.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	198.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.251
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,810.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	379.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.819
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.042
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.418
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	18.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	12.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	17.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	342.000

Call Order: 002 Proposal: E53G0

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45263515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,176.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	320.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.042
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	17.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	38.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.023
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	895.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.707
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.820
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.571
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.278
Section 0003 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.284
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,232.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	113.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	100.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	25.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	3.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	14.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	12.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	10.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	6.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	918.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	822.000