

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05261006	Call Order: 003	Proposal: E52G7	District:05
Counties:	SUMTER			
Road Name:	SR 471			
Limits:	18110000			
Project(s):	45263315201(*)	Federal Aid No:	N/A	
Total Roadway Length:	2.407 Miles	Contract Days:	160	
Total Bridge Length:	0.040 Miles	Letting Date:	10/06/26	
Total Proposal Length:	2.447 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 FLEX	
Proposal Budget Estimate:	\$1,946,171.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, guardrail replacement, signalization improvements and signing and pavement markings on SR 471 from South of Little Withlacoochee River to SR 50, approximately 2.447 miles in Sumter County.

PREQUALIFICATION REQUIRED

Call Order: 003 Proposal: E52G7

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45263315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45263315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,600.000
	0102- 60-	WORK ZONE SIGN	ED	7,520.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,352.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	370.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	348.000
	0102-115-	TYPE III BARRICADE	ED	480.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	160.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,346.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	260.000
	0107- 2-	MOWING	AC	248.200
	0110- 1- 1	CLEARING & GRUBBING (45263315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	21.000
	0120- 6-	EMBANKMENT	CY	36.600
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	7,250.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	24,477.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	12,339.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	3,215.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76	TN	3,635.400
	-22			

Call Order: 003 Proposal: E52G7

ALT	Item	Description	Unit	Quantity
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	46.500
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,027.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,148.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,551.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	18.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.579
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.644
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.062
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45263315201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	6.397
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	370.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45263315201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.579
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.644
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.062
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.080
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.080