

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05261006	Call Order: 004	Proposal: E52G8	District:05
Counties:	VOLUSIA			
Road Name:	SR 46 FROM BREVARD CO LINE TO SEMINOLE COUNTY LINE - PAVEMENT ONLY RESURFACE (FLEX)			
Limits:	79140000			
Project(s):	45264815201(*)	Federal Aid No: N/A		
Total Roadway Length:	5.170 Miles	Contract Days:	80	
Total Bridge Length:	0.266 Miles	Letting Date:	10/06/26	
Total Proposal Length:	5.436 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$2,500,458.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, shoulder treatment, and signing and pavement markings on State Road 46 from the Brevard County Line to the Seminole County Line approximately 5.436 miles in Volusia County.

Marine General Liability Insurance required.

PREQUALIFICATION REQUIRED

Call Order: 004 Proposal: E52G8

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45264815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45264815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,552.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	188.000
	0102-115-	TYPE III BARRICADE	ED	240.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	80.000
	0104- 10- 3	SEDIMENT BARRIER	LF	134.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	58.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	154.380
	0107- 2-	MOWING	AC	138.140
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	91,008.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	10,010.900
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	16,142.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	2,570.400
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45264815201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	15.376
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	3.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	7.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,396.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45264815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	241.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	37.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	21.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	10.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.342
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.185
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.160
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.561
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.513
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.024
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	63.000