

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05260901	Call Order: 004	Proposal: E55E2-R0	District:05
Counties:	ORANGE, SEMINOLE			
Road Name:	Drainage Repair			
Limits:	Midpoint			
Project(s):	44400117219(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/01/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID No.: E55E2
Financial Project No.: 444001-1-72-19
Fiscal Year: 2027
Counties: Seminole and Orange
Contract Calendar Days: 365

This is a Maintenance Work Document Driven Contract with a budget estimate of \$500,000.00. The Contract will be awarded at the budget estimate amount. This contract includes an option for renewal(s).

INTENT AND SCOPE:

The work under this Contract consists of drainage repair including pipe desilting, video inspection, pipe lining, structure cleaning, subsurface pressure grouting, and joint sealing on an as-needed basis on various Department maintained roadways in Orange and Seminole counties.

EXPERIENCE:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

NOTE:

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E55E2-R0				
ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0425- 5-	MANHOLE, ADJUST	EA	20.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	10.000
	0425- 16- 11	DRAINAGE MANHOLE- REPLACE TOP AND RIM	EA	10.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	15.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	15.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	100.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	150.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	150.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	100.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	75.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	50.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	50.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	50.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	25.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	25.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	100.000
	0432- 3- 1	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 15"	EA	100.000
	0432- 3- 2	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 18"	EA	100.000
	0432- 3- 4	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 24"	EA	100.000
	0432- 3- 5	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 30"	EA	50.000
	0432- 3- 6	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 36"	EA	25.000
	0432- 3- 7	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 42"	EA	25.000
	0432- 3- 8	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 48"	EA	30.000
	0432- 3- 9	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 54"	EA	30.000
	0432- 3- 10	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 66"	EA	20.000
	0432- 3- 11	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 60"	EA	20.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	30.000
	0906-173-100	SINGLE COMPONENT POLYURETHANE INJECTION	GA	300.000
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	2,500.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	50.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	8,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	5,000.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	3,000.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	1,500.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	500.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	500.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	400.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	150.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	75.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	30.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	18,000.000