

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 06181129      Call Order: 004      Proposal: E6M08      District:06

Counties: DIST/ST-WIDE, MIAMI-DADE

Road Name: DISTRICTWIDE DRAINAGE PUSHBUTTON PROJECTS - DRAINAGE IMPROV.

Limits: Midpoint

Project(s): 43187137201(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	11/29/18
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

**Description:**

Electronic bids are requested for a contract that consists of providing an efficient and safe operation drainage system and correct any deficiencies within the problem areas as part of the District Storm Water Management System and in compliance with the NPDES program requirements. The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of Letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work. The award will be made at the budgetary ceiling amount of \$400,000.00. Experience in Drainage Repair Form #850-070-05 must be submitted with your bid or your bid may be found non-responsive.

Visit [www.bidx.com](http://www.bidx.com) for more information.

**Call Order: 004 Proposal: E6M08**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0102- 60-	WORK ZONE SIGN	ED	600.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	50.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	50.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,500.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	5.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	25.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	25.000
<b>Section 0002 ASPHALT REPAIR</b>				
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	500.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1,000.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	100.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	25.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000

**Call Order: 004 Proposal: E6M08**

ALT	Item	Description	Unit	Quantity
<b>Section 0003 SODDING</b>				
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	100.000
	E110- 2-	CLEARING & GRUBBING	AC	1.000
<b>Section 0004 CLEAN DRAINAGE STRUCTURES</b>				
	0120- 1-	REGULAR EXCAVATION	CY	75.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	20.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	1.000
	0425- 1-462	INLETS, CURB, TYPE J-6, >10'	EA	1.000
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-571	INLETS, DITCH BOTTOM, TYPE G, <10'	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 1-714	INLETS, GUTTER, TYPE V, J BOTTOM, >10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 4-	INLETS, ADJUST	EA	5.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0425- 8-	DRAINAGE STRUCTURES, MISCELLANEOUS, ADJUST	EA	5.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	5.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	5.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	5.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	500.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	100.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	100.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	50.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	25.000
	0430- 95- 1	OUTFALL BARNACLE REMOVAL, 0 - 24"	LF	500.000
	0430- 95- 2	OUTFALL BARNACLE REMOVAL, 25 - 36"	LF	50.000
	0430- 95- 3	OUTFALL BARNACLE REMOVAL, 37-48"	LF	20.000
	0430- 95- 4	OUTFALL BARNACLE REMOVAL, 49-60"	LF	20.000
	0430- 95- 5	OUTFALL BARNACLE REMOVAL, 61" AND GREATER	LF	10.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	10.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	50.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	10.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	125.000
	E999- 3- 2	HYDRAULIC PUMP, 6"	HR	40.000
<b>Section 0005 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN</b>				
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	20.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	15.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	10.000

**Call Order: 004 Proposal: E6M08**

ALT	Item	Description	Unit	Quantity
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	10.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	10.000
<b>Section 0006 REPAIR CONCRETE SIDEWALKS</b>				
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	75.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	100.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	50.000
<b>Section 0007 PAVEMENT STRIPING</b>				
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.300
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.300
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	800.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	100.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	100.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	5.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.200
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	70.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.300
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	100.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	100.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	100.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	8.000
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	150.000
	E711- 3- 1	PAVEMENT MESSAGES (THERMOPLASTIC)	SF	25.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	800.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	800.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	800.000
<b>Section 0008 RAISED PAVEMENT MARKER REPLACEMENT</b>				
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	50.000