



Florida Department of Transportation

RON DESANTIS
GOVERNOR

1000 NW 111 Avenue
Miami, FL 33172

JARED W. PERDUE, P.E.
SECRETARY

ADDENDUM NO. 1

DATE: December 1st , 2025

TO: PROPOSERS

FROM: Erica Garcia
Procurement Officer
District Six

RE: Project No.: F6015
FIN No.: 454015-1-52-01
Counties: Miami-Dade
Work Description: South Dade Yard CCTV Replacement

I. Answers for Technical Questions

1. Sign-In Sheet:

Please provide a copy of the signed attendance sheet from today's meeting. ---

A: Was provided via email by Procurement Office

2. Outside Pole Specification:

Kindly confirm the exact specifications required for the installation of the exterior pole. –

A: Was provided via email by Procurement Office

3. Network Cabinet Requirements:

Please clarify the type and size of the network cabinets needed for both the Guard House and the Fuel Station. –

A: Key Locking Wall Mounted Enclosures shall be Sized to accommodate Equipment Specified including, F/O Patch Panels, F/O Patch Cables, POE Network Switches, Surge Protection, Power Supplies & Uninterruptible Power Supplies.

4. Equipment Quantities:

Can you provide the **required quantities** for the following equipment? –

- POE switches
- KVM
- Battery backup units
- Fiber patch cords

A: *Please refer to the Technical Scope of Work and (3) Project Drawings CCTV-1 through CCTV-3.*

5. Asphalt Thickness:

Please specify whether the asphalt requirement for this project is **1"** or **2"**? –

A: *Any Existing Surface which is Disturbed, Removed, Cut and/or Patched/Re-Finished shall be restored to be pre-Construction Condition, Including Thickness.*

- 6.** We want to let you know the part # DWC-MB45Wi650T was discontinued and replaced with # DWC-MB45Wi650TW (see attached spec sheet for approval). –

A: *Yes, replacement is acceptable.*

- 7.** Also, please see attached the Pole we recommend for you to consider if it is acceptable and sufficient for your requirements?

A: *The attached Pole specification will be acceptable.*

- 8.** The network switch specified in the bid documents is NOT rack mounted (per the specifications Page #A-20).

- a. According to the riser distribution diagram, you will need (1) rack mounted POE switch with 4 fiber ports and (6) additional POE Switches 2 fiber ports + 8 copper POE Ports. **All of these should be rack mountable.** –

A: *As per specified in A-20 to A-23 of Exhibit "A" Scope of work. Network Switches are not rack mounted.*

- 9. Could you please confirm how you would like the trench to be closed?**
Do you prefer *hot asphalt* or *cold asphalt* for the patch? --

A: *Cold Asphalt for the patch will be acceptable.*

All other documents for the subject project remain unchanged.

Failure to file a Protest within the time prescribed in Section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.