

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 06200430 Call Order: 001 Proposal: E6M37 District:06
 Counties: MIAMI-DADE
 Road Name: SR 922/NE 125 ST
 Limits: 87066000
 Project(s): 44060415201(*) Federal Aid No: N/A
 Total Roadway Length: 0.042 Miles Contract Days: 180
 Total Bridge Length: 0.000 Miles Letting Date: 04/30/20
 Total Proposal Length: 0.042 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120

Proposal Budget Estimate: \$618,926.00

Please read the full advertisement

Description:

Electronic bids are requested for a contract consisting of traffic signals improvements along SR 922/NE 125 Street AT NE 10 Avenue in Miami-Dade County. The summary of pay items for this project is listed in the Plans. Prequalification is required.

Visit www.bidx.com for more information.

Call Order: 001 Proposal: E6M37

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44060415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44060415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	3,540.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,810.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	360.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	73.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	275.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	323.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	0.950
	0107- 2-	MOWING	AC	0.160
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44060415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44060415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44060415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	344.000

Call Order: 001 Proposal: E6M37

ALT	Item	Description	Unit	Quantity
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44060415201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	4.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	4.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,900.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	0.300
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	105.100
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-335	INLETS, CURB, TYPE P-3, PARTIAL	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-431	INLETS, CURB, TYPE J-3, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	128.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	370.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	202.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	231.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	124.000
	0527- 2-	DETECTABLE WARNINGS	SF	53.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	128.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44060415201)	LS	1.000
Section 0002 Signing				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44060415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.017
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	8.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	100.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.150
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.020
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.090
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	668.000

Call Order: 001 Proposal: E6M37

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	27.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	10.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	2.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	4.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207C	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000