

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06200227 Call Order: 003 Proposal: E6M59 District:06

Counties: MONROE

Road Name: 5/US-1/MISSOURI - LITTLE DUCK KEY BRIDGE

Limits: 90030000

Project(s): 43634425201(*)

Federal Aid No: N/A

Total Roadway Length:	0.180 Miles	Contract Days:	100
Total Bridge Length:	0.171 Miles	Letting Date:	02/27/20
Total Proposal Length:	0.351 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$512,588.00

Please read the full advertisement

Description:

Electronic bids are requested for a contract that consists of Miscellaneous Structure along SR 5/US-1/Missouri-Little Duck Key from MM 39.524 to MM 39.704 in Monroe County. Pre-qualification is required.

Visit www.bidx.com for more information.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: E6M59

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43634425201 900103)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	67.700
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	7,828.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	94.000
	0918-349- 4	ULTRA HIGH PERFORMANCE CONCRETE- UHPC, PROJECT 436344-2 -52-01	CY	1.200
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43634425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43634425201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,355.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	805.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	720.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	672.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,170.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	600.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	228.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.029
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.029
	0104- 10- 3	SEDIMENT BARRIER	LF	1,313.000
	0107- 1-	LITTER REMOVAL	AC	5.760
	0107- 2-	MOWING	AC	3.440
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	5,396.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	219.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	207.200
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.730
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.728
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43634425201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.435
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43634425201)	LS	1.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.543
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.073
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.136
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.342
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.171
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.171