

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06220825 Call Order: 001 Proposal: E6M36 District:06

Counties: MIAMI-DADE

Road Name: SR A1A/MACARTHUR CSWY FR BISCAYNE BLVD TO ALTON RD

Limits: 87060000

Project(s): 44343215201(*) Federal Aid No: N/A

Total Roadway Length:	2.717 Miles	Contract Days:	160
Total Bridge Length:	0.000 Miles	Letting Date:	08/25/22
Total Proposal Length:	2.717 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90

Proposal Budget Estimate: \$963,761.00

Please read the full advertisement

Description:

Electronic bids are requested for a contract consisting of Bike Path/Trail improvements along SR A1A/ Macarthur CWY from East of SR5 / Biscayne BLV to West of SR907/ Alton RD in Miami Dade County. Prequalification is required.

Visit www.bidx.com for more information.

Call Order: 001 Proposal: E6M36

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44343215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44343215201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44343215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,960.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	75.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	696.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,880.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	120.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	360.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	360.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	84.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	70.000
	0107- 1-	LITTER REMOVAL	AC	53.340
	0107- 2-	MOWING	AC	32.920
	0110- 1- 1	CLEARING & GRUBBING (44343215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	202.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44343215201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	182.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	87.000

Call Order: 001 Proposal: E6M36

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	41.000
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	12.000
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	10.500
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-925	INLETS, ADJACENT BARRIER, PARTIAL	EA	3.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	13.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	351.000
	0520- 1- 11	CONCRETE CURB & GUTTER, VARIABLE HEIGHT TYPE F	LF	110.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	58.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	156.000
	0527- 2-	DETECTABLE WARNINGS	SF	50.000
	0536- 73-	GUARDRAIL REMOVAL	LF	165.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	404.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44343215201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	17.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	9.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0701- 18-101	PROFIED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	3.588
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	1,064.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,074.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44343215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,351.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	55.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.647
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	75.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	60.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	71.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	33.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	7.049
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	9,672.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.878
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	2,531.000

Call Order: 001 Proposal: E6M36

ALT	Item	Description	Unit	Quantity
	0920-714- 32	GREEN COLORED PAVEMENT MARKINGS, BIKE LANE, PROJECT 443432-1-52-01	SF	11,798.000
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	860.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,837.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,595.000
	0715- 61-411	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 8' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715-500- 11	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL	EA	2.000
	0715-540-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, RELOCATE	EA	1.000