

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06220526 Call Order: 001 Proposal: E6L20 District:06

Counties: MONROE

Road Name: SR A1A/S. ROOSEVELT BLVD

Limits: 90003000

Project(s): 25054885201(*) Federal Aid No: N/A
 Project(s): 25054885601 Federal Aid No: N/A
 Project(s): 25054895201 Federal Aid No: N/A
 Project(s): 44389215201 Federal Aid No: D621054B
 Project(s): 44389215202 Federal Aid No: N/A
 Project(s): 44390015201 Federal Aid No: N/A
 Project(s): 44600715201 Federal Aid No: N/A

Total Roadway Length:	3.990 Miles	Contract Days:	800
Total Bridge Length:	0.000 Miles	Letting Date:	05/26/22
Total Proposal Length:	3.990 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$21,690,545.00

Please read the full advertisement

Description: Incentive / Disincentive

Electronic bids are requested for an Incentive-Disincentive contract that consists of Widen & Resurface Existing Lanes along SR A1A / South Roosevelt BLVD from Bertha Street to End of Smathers Beach. Resurfacing along SR 5/ Whitehead Street from Fleming Street to West of Truman Ave. Pavement Only Resurface (Flex) along SR 5/ Frontage Road at Boca Chica Key. Resurfacing Ride Only along SR A1A / South Roosevelt BLVD from Go Lane to North of Roosevelt BLVD and Traffic Operations Improvement along SR A1A / South Roosevelt BLVD from East of La Brisa to East of Key West of the Sea in Monroe County. The summary of pay items for this project is listed in the plans. Prequalification is required.

Visit www.bidx.com for more information.

Call Order: 001 Proposal: E6L20

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (25054885201)	LS	1.000
	0101- 1-	MOBILIZATION (44389215201)	LS	1.000
	0101- 1-	MOBILIZATION (44390015201)	LS	1.000
	0101- 1-	MOBILIZATION (44600715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (25054885201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44389215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44390015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44600715201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	69.100
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (25054885201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	544.000
	0102- 60-	WORK ZONE SIGN	ED	63,952.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	4,030.000

Call Order: 001 Proposal: E6L20

ALT	Item	Description	Unit	Quantity
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	5,642.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	67,525.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,558,680.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	885.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	22.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,564.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	570.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	570.000
	0102-115-	TYPE III BARRICADE	ED	5,740.000
	0104- 10- 3	SEDIMENT BARRIER	LF	8,795.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	67.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	116.000
	0107- 1-	LITTER REMOVAL	AC	371.770
	0107- 2-	MOWING	AC	202.300
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (25054885201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44389215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (25054885201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44389215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44390015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	10,462.000
	0110- 5-	PLUGGING WATER WELLS, ARTESIAN	EA	5.000
	0110- 21-	TREE PROTECTION BARRIER	LF	6,926.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	140.000
	0110- 23-	TREE REMOVAL	EA	30.000
	0120- 1-	REGULAR EXCAVATION	CY	1,879.800
	0120- 4-	SUBSOIL EXCAVATION	CY	25.000
	0120- 6-	EMBANKMENT	CY	2,735.600
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44389215201)	LS	1.000
	0121- 70-	FLOWABLE FILL	CY	34.900
	0160- 4-	TYPE B STABILIZATION	SY	629.000
	0210- 1- 1	REWORKING LIMEROCK BASE, 6"	SY	1,415.000
	0210- 1- 8	REWORKING LIMEROCK BASE, 4"	SY	2,497.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	225.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	1,095.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	48.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	154.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	1,165.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	20,034.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	5,617.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	22,710.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	877.700
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6,485.000

Call Order: 001 Proposal: E6L20

ALT	Item	Description	Unit	Quantity
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	649.800
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	871.800
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,399.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	18.300
	0400- 3- 20	CONC CLASS III, SEAL	CY	242.100
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	40.200
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	154.500
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	25,082.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	5,841.000
	0425- 1-202	INLETS, CURB, TYPE 9, >10'	EA	2.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	13.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	3.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	4.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	7.000
	0425- 1-362	INLETS, CURB, TYPE P-6, >10'	EA	2.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	2.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	8.000
	0425- 1-455	INLETS, CURB, TYPE J-5, PARTIAL	EA	1.000
	0425- 1-462	INLETS, CURB, TYPE J-6, >10'	EA	4.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	6.000
	0425- 1-522	INLETS, DT BOT, TYPE C, >10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 42	MANHOLES, P-7, >10'	EA	1.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 2- 75	MANHOLES, J-7, >10' CONTROL STRUCTURE	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	31.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	1,693.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	1,368.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,069.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,328.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	405.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	106.000
	0444- 70- 11	DEEP WELL- OPEN HOLE, 24"	LF	320.000
	0444- 71- 11	DEEP WELL CASING, 24"	LF	480.000
	0444- 73- 12	STEEL WELL GRATE, 24" AND GREATER	EA	8.000
	0444- 74- 1	DEEP WELL INJECTION BOX, STRUCTURE WITH NO OUTFLOW	EA	8.000
	0448- 73-	PUMPING STATION- DRAINAGE (25054885201)	LS	1.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	22,267.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	141.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	9,192.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	6.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	325.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	9,230.000

ALT	Item	Description	Unit	Quantity
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	835.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	12.000
	0527- 2-	DETECTABLE WARNINGS	SF	722.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,446.600
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	15.000
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	82.000
	0530- 74-	BEDDING STONE	TN	337.100
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	391.000
	0536- 73-	GUARDRAIL REMOVAL	LF	86.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0550- 10-212	FENCING, TYPE B, 0.5-5.0', W/ VINYL COATING	LF	142.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,030.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (25054885201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,049.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.242
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.028
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,955.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	810.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	695.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.820
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	42.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.844
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	299.000
	0710- 11-421	PAINTED PAVEMENT MARKINGS, STANDARD, BLUE, SOLID FOR PARKING LOT- ACCESSIBLE MARKINGS, 6"	LF	160.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25054885201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44389215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44390015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44600715201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	101.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	30.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	49.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	19.000

ALT	Item	Description	Unit	Quantity
	0700- 11-121	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, ELECTRONIC REGULATORY SIGN, UP TO 12 SF	AS	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	7.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,489.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	16.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (25054885201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44389215201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44390015201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44600715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,663.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,429.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	452.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	11.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	651.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	505.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,400.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	46.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.583
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.095
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10 -30 SKIP OR 3-9 LANE DROP	GM	1.625
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.039
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.505
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	330.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,600.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,650.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	3.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	1.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	71.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	72.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44389215202)	LS	1.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,738.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	54.000

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	69.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	6.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	640.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	6.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	13.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	4.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	13.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	5.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	12.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	9.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	6.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	14.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	12.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207C	AS	3.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	3.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	6.000
Section 0005 Landscape / Peripheral				
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (44389215201)	LS	1.000
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (44390015201)	LS	1.000
	0581- 1- 2	RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	EA	5.000
Section 0006 Utilities				
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (25054885601)	LS	1.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	13.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	346.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	344.000

Call Order: 001 Proposal: E6L20

ALT	Item	Description	Unit	Quantity
	1050- 18-002	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 2- 4.9"	LF	17.000
	1050- 18-003	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 5- 7.9"	LF	16.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	1,922.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	105.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	2,260.000
	1050- 41-202	UTILITY PIPE- POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	21.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	32.000
	1055- 51-212	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 12"	EA	5.000
	1055- 51-512	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 12"	EA	24.000
	1080- 23-106	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 6"	EA	5.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	6.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	5.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	8.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	3.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	85.000
Section 0007 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.313
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	2.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	52.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	140.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000
	0684- 6- 30	WIRELESS COMMUNICATION DEVICE, INSTALL	EA	3.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25054895201)	LS	1.000