

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting: 06221117      Call Order: 001      Proposal: E6O04      District:06

Counties: MIAMI-DADE

Road Name: SR 856 RAMP NB A1A TO SR 856 (BRIDGE #870603) - REPAIR/REHAB

Limits: 87210005

Project(s): 44196515201(\*)

Federal Aid No: N/A

Total Roadway Length:	0.259 Miles	Contract Days:	380
Total Bridge Length:	0.258 Miles	Letting Date:	11/17/22
Total Proposal Length:	0.517 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$2,588,373.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of Bridge-Repair / Rehabilitation along SR 856 RAMP NB A1A to SR 856 (Bridge 870603). Prequalification is required.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E6004**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	32,651.000
	0401- 70-108	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR - STYRENE-BUTADIENE, PROJECT 441965-1-52-01	CF	29.000
	0413-151-	METHACRYLATE MONOMER	GA	591.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	58,964.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	327.000
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	81.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	2.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44196515201 870603)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44196515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44196515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,021.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,145.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	18,648.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	234.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	700.000
	0102-115-	TYPE III BARRICADE	ED	1,626.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.270
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.070
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.260
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44196515201)	LS	1.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	108.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	5.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.270
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.070
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.260