

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	06220929	Call Order: 001	Proposal: E6O02	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 90/US 41 OVER SPILLWAY BRIDGE-REPAIR/REHABILITATION			
Limits:	87110000			
Project(s):	44479815201	Federal Aid No: N/A		
Project(s):	44479915201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.080 Miles	Contract Days:	200	
Total Bridge Length:	0.064 Miles	Letting Date:	09/29/22	
Total Proposal Length:	0.144 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90	
Proposal Budget Estimate:	\$616,814.00			

Please read the full advertisement

Description:

Electronic bids are requested for a contract that consists of Bridge Repair/Rehabilitation along SR 90/US 41 Over Spillway 12-D Bridge# 870031 and Over Spillway 12-B Bridge# 870028 in Miami-Dade County. Prequalification is required.

Visit www.bidx.com for more information.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E6002

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,400.000
	0400-142- 3	CATHODIC PROTECTION SYSTEM, ZINC ALUMINUM SPRAY	SF	896.000
	0401- 70-109	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR - STYRENE-BUTADIENE, PROJECT 444798-1-52-01	CF	16.700
	0401- 70-110	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR - STYRENE-BUTADIENE, PROJECT 444799-1-52-01	CF	10.000
	0403- 1- 20	EPOXY CONCRETE OVERLAY FOR CONCRETE BRIDGE DECKS, PROJECTS 444798-1-52-01 AND 444799-1-52-01	SY	1,306.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	2.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	35.000
	0457- 2-121	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	94.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44479815201)	LS	1.000
	0101- 1-	MOBILIZATION (44479915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44479815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44479915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,150.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,310.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	416.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	180.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.320
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.320
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44479815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44479915201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	24.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.160
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.160