

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 06230126 Call Order: 002 Proposal: E6O13 District:06

Counties: MIAMI-DADE

Road Name: SR A1A /COLLINS AVE - TRAFFIC OPS IMPROVEMENT

Limits: 87060000

Project(s): 44890615201(*) Federal Aid No: N/A

| | | | |
|------------------------|-------------|----------------------------|----------|
| Total Roadway Length: | 0.157 Miles | Contract Days: | 140 |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 01/26/23 |
| Total Proposal Length: | 0.157 Miles | Contract Execution Days: | 10 |
| | | Special Start Date: | N/A |
| | | Aquis/Flexible Start Time: | 90 |

Proposal Budget Estimate: \$510,434.00

Please read the full advertisement

Description:

A Contract that consists of Traffic Ops Improvement along SR A1A / Collins Avenue from Harbour Way West to South of Bal Bay Drive. Pre-qualification is required.

Call Order: 002 Proposal: E6O13

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (44890615201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44890615201) | LS | 1.000 |
| | 0102- 4- 1 | PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44890615201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 5,845.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 4,060.000 |
| | 0102- 74- 8 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD | 22,022.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 210.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 322.000 |
| | 0102-913- 24 | REMOVABLE TAPE, WHITE, 12" CROSSWALK | LF | 138.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 6.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 2.010 |
| | 0107- 2- | MOWING | AC | 0.310 |
| | 0110- 1- 1 | CLEARING & GRUBBING (44890615201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 158.000 |
| | 0110- 21- | TREE PROTECTION BARRIER | LF | 228.000 |
| | 0120- 2- 2 | BORROW EXCAVATION, TRUCK MEASURE | CY | 94.500 |
| | 0120- 71- | REGULAR EXCAVATION (3-R PROJECTS ONLY) (44890615201) | LS | 1.000 |
| | 0327- 70- 6 | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH | SY | 1,984.000 |
| | 0334- 1- 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 17.800 |
| | 0337- 7- 82 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22 | TN | 163.700 |
| | 0425- 5- | MANHOLE, ADJUST | EA | 2.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 496.000 |
| | 0520- 2- 4 | CONCRETE CURB, TYPE D | LF | 80.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 48.000 |

Call Order: 002 Proposal: E6013

| ALT | Item | Description | Unit | Quantity |
|-----------------------------------|--------------|---|------|----------|
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 67.000 |
| | 0526- 1-101 | PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL | SY | 2.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 68.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 323.000 |
| | 0920-520- 3 | RAISED CROSSWALK, TYPE RC CURB WITH PLATE/GRATE, PROJECT 448906-1-52-01 | LF | 48.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44890615201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 6.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 6.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 8.000 |
| | 0705- 11- 1 | DELINEATOR, FLEXIBLE TUBULAR | EA | 49.000 |
| | 0706- 1- 3 | RAISED PAVEMENT MARKER, TYPE B | EA | 40.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44890615201) | LS | 1.000 |
| | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND | GM | 0.162 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 95.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 92.000 |
| | 0711- 11-130 | THERMOPLASTIC, STANDARD, WHITE, VERTICAL DEFLECTION MARKING | EA | 2.000 |
| | 0711- 11-140 | THERMOPLASTIC, STANDARD, WHITE, VERTICAL DEFLECTION ADVANCE WARNING MARKING | EA | 2.000 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 9.000 |
| | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK | LF | 66.000 |
| | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE | EA | 3.000 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 0.241 |
| | 0711- 16-133 | THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP | GM | 0.053 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 0.104 |
| Section 0003 Lighting | | | | |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 145.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 3.000 |
| | 0715- 1- 12 | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6 | LF | 952.000 |
| | 0715- 1- 60 | LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS | LF | 390.000 |
| | 0715-500- 11 | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL | EA | 2.000 |
| | 0715-511-130 | LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 30' | EA | 1.000 |
| Section 0004 Signalization | | | | |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 4.000 |
| | 0654- 2- 28 | MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR | AS | 4.000 |