

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06230126 Call Order: 005 Proposal: E6O51-R0 District:06

Counties: MIAMI-DADE

Road Name: CONCRETE INSTALL MIAMI DADE COUNTY - ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 44428437201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	01/26/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$350,000.00

Please read the full advertisement

Description:

A contract that consists of construction, re-construction and removal of concrete sidewalk, driveways, curb cut ramps, curb & gutter on various Arterial State Roads.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Budgetary Ceiling amount of \$350,000.00

Call Order: 005 Proposal: E6O51-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CONCRETE SIDEWALK REPAIR (SY)				
	0102- 60-	WORK ZONE SIGN	ED	250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	250.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	250.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,990.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	300.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F ("Colored Concrete")	LF	100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,700.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK ("Colored Concrete")	SY	70.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	750.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK ("Colored Concrete")	SY	70.000
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	25.000
	E102- 74- 9	TRAFFIC CONES	ED	3,500.000