

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06230727 Call Order: 004 Proposal: E6P02 District:06

Counties: MIAMI-DADE

Road Name: SHOULDER REPAIR MIAMI-DADE COUNTY - ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 44425237201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	07/27/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$150,000.00

Please read the full advertisement

Description:

A contract that consists of shoulder preparation (restoring non-paved shoulder, slopes and roadside ditches) for proper drainage, protection of pavement edge, and to provide a safe recovery area. This contract also consists of furnishing and placing sod, rolling, fertilizing, watering, and maintaining the sodded areas to ensure a healthy stand of grass in different locations on various Arterial State Roads.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Budgetary Ceiling amount of \$150,000.00.

Call Order: 004 Proposal: E6P02

ALT	Item	Description	Unit	Quantity
Section 0001 REWORK NONPAVE SHOULDER (AC)				
	0102- 60-	WORK ZONE SIGN	ED	1,680.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,680.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	420.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	80.000
	E102- 74- 9	TRAFFIC CONES	ED	8,400.000
	E570- 5-	FERTILIZER	TN	5.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	100.000
	E575- 1-	SODDING	SY	25,000.000
	E577- 70-	SHOULDER REWORK	SY	25,000.000
	E577- 70- 1	REWORKING SHOULDERS (SPOT REPAIRS)	SY	1,000.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	26,400.000