

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 06231026 Call Order: 001 Proposal: E6O85 District:06

Counties: MIAMI-DADE

Road Name: TRAFFIC OPS PUSH-BUTTON ROADS MISC. CONSTRUCTION

Limits: Midpoint

Project(s): 44626345201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	10/26/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$2,000,000.00

Please read the full advertisement

Description:

This Contract consist of Traffic Operations Push-Button Roadway Miscellaneous Construction at various locations. Pre-qualification is required.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

This contract has a department advertised estimate amount of \$2,000,000.

Call Order: 001 Proposal: E6O85

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	300.000
	0102- 60-	WORK ZONE SIGN	ED	7,200.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	200.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	500.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	600.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	200.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	500.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,000.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	200.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	400.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	250.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	10.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,000.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	200.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-115-	TYPE III BARRICADE	ED	400.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	40.000
	0107- 1-	LITTER REMOVAL	AC	10.000
	0107- 2-	MOWING	AC	10.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	4.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	2.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,000.000
	0110- 21-	TREE PROTECTION BARRIER	LF	100.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	10.000
	0120- 1-	REGULAR EXCAVATION	CY	700.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	500.000
	0160- 4-	TYPE B STABILIZATION	SY	4,000.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,500.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	500.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	500.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	200.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	7,000.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	3,000.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	5,000.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	2,000.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	500.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	500.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	300.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	600.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	600.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	300.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	60.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	2.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 1-571	INLETS, DITCH BOTTOM, TYPE G, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	50.000

Call Order: 001 Proposal: E6O85

ALT	Item	Description	Unit	Quantity
	0425- 6-	VALVE BOXES, ADJUST	EA	50.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	200.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	200.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	200.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	200.000
	0430-175-215	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 15"S/CD	LF	16.000
	0430-982-623	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 15" CD	EA	2.000
	0443- 70- 3	FRENCH DRAIN, 18"	LF	200.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	200.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	500.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	20.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	850.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	500.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	250.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	500.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	250.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	100.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,500.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	500.000
	0523- 3-	PATTERNED PAVEMENT	SY	300.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	40.000
	0527- 2-	DETECTABLE WARNINGS	SF	250.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	2,000.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,000.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	400.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	5.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	100.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	5.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	5.000
	0536- 73-	GUARDRAIL REMOVAL	LF	200.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	4.000
	0538- 1-	GUARDRAIL RESET	LF	100.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,000.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	1.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,200.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	500.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,000.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.250
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	20.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.000
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	300.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	100.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	50.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	2.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	5.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	5.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	5.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	5.000
	0700- 1- 33	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 21-30 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	25.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	50.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	1.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	2.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	40.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	10.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	1.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	1.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	1.000
	0700- 3-107	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 201-300 SF	EA	1.000
	0700- 3-108	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 301-400 SF	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	5.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	1.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	1.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-301	SIGN PANEL, FURNISH & INSTALL SINGLE POST BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	EA	2.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	20.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	15.000
	0700- 3-503	SIGN PANEL, RELOCATE, 21-30 SF	EA	2.000
	0700- 3-504	SIGN PANEL, RELOCATE, 31-50 SF	EA	2.000
	0700- 3-505	SIGN PANEL, RELOCATE, 51-100 SF	EA	2.000
	0700- 3-506	SIGN PANEL, RELOCATE, 101-200 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	25.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	20.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	2.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	4.000
	0700- 4-140	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT	EA	4.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	4.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	10.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	10.000
	0700-141-111	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-141-121	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/2 BEACONS, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-141-131	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/EDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0700-141-132	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/EDS, 12-20 SF OF STATIC SIGN PANELS	EA	2.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	2.000
	0700-141-360	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, BLANK OUT SIGN <12 SF	EA	5.000
	0700-141-610	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, RETROFIT EXISTING OVERHEAD MOUNT, 1 BEACON	EA	4.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0700-141-620	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, RETROFIT EXISTING OVERHEAD MOUNT, 2 BEACONS	EA	3.000
	0700-141-902	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - GROUND MOUNT	EA	5.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-142-121	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/2 BEACONS, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-142-131	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-132	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, 12-20 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-140	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	2.000
	0700-142-901	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE BEACON(S), SIGN TO REMAIN	EA	4.000
	0701- 17-101	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	1.000
	0701- 17-201	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SOLID,6"	GM	1.000
	0701- 17-221	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SKIP,6"	GM	1.000
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	50.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	50.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	600.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	50.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	800.000
	0706- 1-110	RAISED PAVEMENT MARKER, TYPE F INTERNALLY ILLUMINATED	EA	100.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	200.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.500
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,200.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	600.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,000.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.500
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	50.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	50.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	50.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	250.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.500

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	1.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	1.000
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	4.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	4.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	1.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	1.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	2,000.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,500.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	500.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT RAILROAD DYNAMIC ENVELOPE	LF	600.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.000
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.000
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	1.000
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.000
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.000
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	1.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	1.000
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	2,000.000
	0713-103-133	PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES	GM	1.000
	0713-103-333	PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES	GM	1.000
Section 0003 Lighting				
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	400.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	400.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	4,000.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	12.000
	0715- 61-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	2.000
	0715- 62-411	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT, 8' ARM LENGTH	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	8.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	200.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	500.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	100.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	2,000.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0632- 7- 7	SIGNAL CABLE, REMOVE- OUTSIDE OF INTERSECTION	LF	100.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	50.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	2.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	500.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	500.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	2.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0646- 1- 30	ALUMINUM SIGNALS POLE, INSTALL	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0646- 2-115	ALUMINUM POLE- INDEX 695-001, FURNISH & INSTALL, 15'	EA	1.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	1.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0649- 40- 4	STEEL MAST ARM ASSEMBLY- REPLACE STRUCTURAL GROUT PAD ON EXISTING POLE	EA	1.000
	0650- 1- 11	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	4.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	2.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000
	0650- 1- 44	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL PROGRAMMABLE, 3 SECTION, 1 WAY	AS	2.000
	0650- 1- 46	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL PROGRAMMABLE, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 48	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL PROGRAMMABLE, 5 SECTION- STRAIGHT, 1 WAY	AS	1.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	4.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	4.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	4.000
	0650- 2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	4.000
	0650- 2-106	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- 12" LED STANDARD MODULE	EA	4.000
	0650- 2-108	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, ADD SECTION TO EXISTING SIGNAL ASSEMBLY	EA	2.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0654- 2- 11	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	2.000
	0654- 2- 12	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000
	0654- 2- 15	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC POWER, MAST ARM MOUNT RRFB SIGN ASSEMBLY	AS	2.000
	0654- 2- 16	MIDBLOCK CROSSWALK:RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC POWER, POLE MOUNT RRFB SIGN ASSEMBLY	AS	2.000
	0654- 2- 21	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSY- SINGLE DIRECTION	AS	2.000
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000

Call Order: 001 Proposal: E6085

ALT	Item	Description	Unit	Quantity
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	4.000
	0659- 1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	2.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	8.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	4.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	2.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207C	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0684- 90-102	NETWORK DEVICE, CELLULAR MODEM	EA	2.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000