

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 06230928      Call Order: 002      Proposal: E6074      District:06

Counties: MIAMI-DADE

Road Name: SR 913 RAMP WB TO I-95 NB & TO US-1 870162 - 870163

Limits: 87270167

Project(s): 44480115201(\*)      Federal Aid No: N/A

Project(s): 44480215201      Federal Aid No: N/A

Total Roadway Length:	0.297 Miles	Contract Days:	340
Total Bridge Length:	0.298 Miles	Letting Date:	09/28/23
Total Proposal Length:	0.595 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$6,953,837.00

Please read the full advertisement

Description:

A contract consisting of Bridge Painting along SR 913 Ramp Westbound to I-95 Northbound Bridge #870162 and Westbound to US-1 Southbound Bridge #870163 in Miami Dade County.

**Call Order: 002 Proposal: E6074**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44480115201 870162)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44480215201 870163)	LS	1.000
	0110- 12- 1	HYDRODEMOLITION, REMOVAL OF DECK SURFACE	SY	1,163.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	1,163.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	1,163.000
	0400- 20-	GRINDING BRIDGE DECK- REHABILITATION	SY	1,163.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	34,181.000
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	24.500
	0405- 70- 9	LATEX MODIFIED CONCRETE, VERY EARLY STRENGTH	CF	1,816.400
	0413-151-	METHACRYLATE MONOMER	GA	356.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	34,612.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	10,000.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	189.000
	0458- 1- 25	BRIDGE DECK EXPANSION JOINT, REHABILITATION, COMPRESSION ELASTOMERIC	LF	81.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	62.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44480115201 870162)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44480215201 870163)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44480115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44480215201)	LS	1.000

**Call Order: 002 Proposal: E6074**

ALT	Item	Description	Unit	Quantity
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44480115201)	LS	1.000
	0101- 1-	MOBILIZATION (44480215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44480115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44480215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	168.000
	0102- 60-	WORK ZONE SIGN	ED	10,719.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,663.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,878.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	194.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	614.000
	0102-115-	TYPE III BARRICADE	ED	1,313.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	112.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	44.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.305
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.041
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.038
	0713-103-133	PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES	GM	0.051
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.298
	0713-103-333	PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES	GM	0.051