Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 06240829 Call Order: 002 Proposal: E6P37-R0 District:06

Counties: MIAMI-DADE

Road Name: CONCRETE INSTALLATION MIAMI-DADE COUNTY-ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 42823557201(*) Federal Aid No: N/A

Total Roadway Length:0.000 MilesContract Days:365Total Bridge Length:0.000 MilesLetting Date:08/29/24

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time:

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

Description:

This is a construction, reconstruction and removal of concrete sidewalk, driveways, curb cut ramps, curb & gutter, special curb & gutter, and sound/noise barrier panels on various Arterial State Roads in Miami-Dade County. The summary of pay items for this project is listed in the Bid Price Proposal.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Department Advertised Estimate Amount of \$400,000.00.

Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

		Call Order: 002 Proposal: E6P37-R0		
ALT	Item	Description	Unit	Quantity
Sectio	n 0001 CONCRE	TE SIDEWALK REPAIR (SY)		
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0110- 4-10	REMOVAL OF EXISTING CONCRETE	SY	3,439.000
	0120- 6-	EMBANKMENT	CY	50.000
	0401-70-4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	5.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	100.000
	0520- 1-10	CONCRETE CURB & GUTTER, TYPE F	LF	250.000
	0520- 1-10	CONCRETE CURB & GUTTER, TYPE F (Colored Concrete)	LF	100.000
	0520- 1-12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	40.000
	0520- 1-12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE (Colored Concrete)	LF	50.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	25.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,250.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK (Colored Concrete)	SY	800.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	690.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK (Colored Concrete)	SY	595.000
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	0635- 2-11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0635- 2-30	PULL & SPLICE BOX, INSTALL	EA	5.000
	E575- 1-	SODDING	SY	75.000