

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 06240125 Call Order: 004 Proposal: E6P09 District:06

Counties: MIAMI-DADE

Road Name: SR 25/NW 36 ST from NW 27 AVE to NW 22 AVE

Limits: 87090000

Project(s): 45116815201(*) Federal Aid No: N/A

Total Roadway Length:	0.958 Miles	Contract Days:	200
Total Bridge Length:	0.000 Miles	Letting Date:	01/25/24
Total Proposal Length:	0.958 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$1,469,980.00

Please read the full advertisement

Description:

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF DRAINAGE IMPROVEMENTS ALONG SR 25/NW 36 STREET FROM NW 27 AVENUE TO NW22 AVENUE IN MIAMI-DADE COUNTY.

PRE-QUALIFICATION IS REQUIRED FOR THIS CONTRACT.

Call Order: 004 Proposal: E6P09

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45116815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45116815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,440.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	580.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	825.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	29,350.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	32,800.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	400.000
	0102-115-	TYPE III BARRICADE	ED	1,690.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	21.000
	0107- 1-	LITTER REMOVAL	AC	6.910
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	15,012.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,032.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	1,032.100
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	2.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	2.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	1.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	8.000
	0425- 5-	MANHOLE, ADJUST	EA	9.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	4.000

Call Order: 004 Proposal: E6P09

ALT	Item	Description	Unit	Quantity
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	43.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	248.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	1,075.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,990.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.835
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.597
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45116815201)	LS	1.000
Section 0002 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	604.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45116815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	105.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	887.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	20.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.051
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	269.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	25.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.999
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	0.801
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.397