

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 06240328      Call Order: 001      Proposal: E6O81      District:06

Counties: MIAMI-DADE

Road Name: SR 93/I-75 FROM SR 826 TO RAMP 87075616 - RESURFACING

Limits: 87075000

Project(s): 44598815201(\*)      Federal Aid No: N/A

Total Roadway Length:	1.912 Miles	Contract Days:	250
Total Bridge Length:	0.646 Miles	Letting Date:	03/28/24
Total Proposal Length:	2.558 Miles	Contract Execution Days:	10
		Special Start Date:	01/06/25
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$3,518,379.00

Please read the full advertisement

Description: Incentive / Disincentive

This is an Incentive-Disincentive contract that consists of Resurfacing along SR 93/I-75 from SR 826 to ramp 87075616 in Miami-Dade County. Prequalification is required.

**Call Order: 001 Proposal: E6O81**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 12- 1	HYDRODEMOLITION, REMOVAL OF DECK SURFACE	SY	52.000
	0400- 32-	CONCRETE FOR JOINT REPAIR	CY	18.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	80.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	3,200.000
	0458- 1- 24	BRIDGE DECK EXPANSION JOINT, REHABILITATION, FINGER JOINT	LF	228.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44598815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44598815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,715.000
	0102- 60-	WORK ZONE SIGN	ED	11,880.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,438.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	1,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	61,020.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	670.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	650.000
	0102-115-	TYPE III BARRICADE	ED	1,080.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	600.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,023.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0107- 1-	LITTER REMOVAL	AC	195.940
	0107- 2-	MOWING	AC	186.930
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44598815201)	LS	1.000

**Call Order: 001 Proposal: E6081**

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44598815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	110.700
	0120- 4-	SUBSOIL EXCAVATION	CY	610.900
	0120- 6-	EMBANKMENT	CY	2,168.400
	0160- 4-	TYPE B STABILIZATION	SY	494.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	212.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,217.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	15,920.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	120.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	481.500
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	1,381.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	662.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	31.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	822.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	770.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 1	PERFORMANCE TURF	SY	3,558.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	845.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	764.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.300
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.301
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.856
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	17.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.494
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	412.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44598815201)	LS	1.000
<b>Section 0003</b>	<b>Signing</b>			
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.620
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	7.000
	0700- 1-312	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE- MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-402	SIGN PANEL, INSTALL, 12-20 SF	EA	13.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	13.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	562.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44598815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	575.000

**Call Order: 001 Proposal: E6081**

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	5.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	412.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.803
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.301
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.613
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.763
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.228
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.150
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.646
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.146
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	5,341.000