

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 06241121      Call Order: 002      Proposal: E6P14      District:06

Counties: MIAMI-DADE

Road Name: IMPVMENT CONSIST OF BRIDGE PAINT SR-970 F US1 TO I-95NB.

Limits: 87006000

Project(s): 44775115201(\*)

Federal Aid No: N/A

Total Roadway Length:	0.432 Miles	Contract Days:	360
Total Bridge Length:	0.674 Miles	Letting Date:	11/21/24
Total Proposal Length:	1.106 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$2,730,686.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of the bridge painting along SR-970/Downtown Distributor from US-1 to I-95 NB Bridge 870475 in Miami-Dade County. Pre-qualification is required.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E6P14**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0103- 1-100	TEMPORARY WORK STRUCTURE (44775115201 870475)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44775115201 870475)	LS	1.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	2.100
	0400-140- 1	NEOPRENE PAD REPLACEMENT, BENT/PIER	EA	11.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	184.800
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	4.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	329.000
	0413-151-	METHACRYLATE MONOMER	GA	101.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	10,003.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	688.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,162.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	0.200
	0460- 1- 1	STRUCT STEEL- REHAB, CARBON	LB	2,483.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44775115201 870475)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44775115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44775115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	19,790.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	42,770.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	240.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	320.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,712.000
	0102-115-	TYPE III BARRICADE	ED	1,220.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44775115201)	LS	1.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	262.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	73.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.683
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.075
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.478
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.687