

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06241031 Call Order: 002 Proposal: E6P44 District:06
Counties: MIAMI-DADE
Road Name: STRIPING PREFORMED MIAMI-DADE COUNTY - ROUTINE MAINTENANCE
Limits: Midpoint
Project(s): 44094957201(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 730
Total Bridge Length: 0.000 Miles Letting Date: 10/31/24
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time:

Proposal Budget Estimate: \$340,000.00

Please read the full advertisement

Description:

A contract to apply preformed thermoplastic pavement markings and permanent tape pavement markings in different locations on various sections of state roads in Miami Dade County. This contract is not renewable.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each item to be bid. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific site are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to accomplished, and the number calendar days to complete the work.

The Award will be made at the Department Advertised Estimate amount of \$340,000.00.

***Experience in Pavement Markings (Form No. 850-070-06) must be submitted with your bid as an attachment, or the bid may be deemed non-responsive.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 002 Proposal: E6P44

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	6,000.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,500.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	40.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	85.000
	0711- 18-101	THERMOPLASTIC, PREFORMED, YELLOW, SOLID, 18" FOR CHEVRONS ON CONCRETE- MAINTENANCE USE ONLY	LF	500.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.250
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.600
	0713-103-141	PERMANENT TAPE, WHITE, 6-10 SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.250
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.750
	0713-103-271	PERMANENT TAPE, YELLOW, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.750
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.750
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.750
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	40,000.000