

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	06240926	Call Order: 001	Proposal: E6P40-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	ASPHALT REPAIR MIAMI DADE COUNTY - ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	44602117201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/26/24	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$251,000.00

Please read the full advertisement

Description:

This Contract consists of repair of existing asphalt pavement on various Arterial State Roads in Miami-Dade County. The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Experience in Asphalt Paving Form #850-070-01 must be submitted as an attachment with your bid or your bid will be found non-responsive.

Award will be made at the Department Advertised Estimate Amount of \$251,000.00.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E6P40-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0102- 60-	WORK ZONE SIGN	ED	70.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	350.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	16.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	10.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	10.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	20.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	8,500.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	678.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	5.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 16- 11	DRAINAGE MANHOLE- REPLACE TOP AND RIM	EA	1.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	3.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.100
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	300.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	200.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	250.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	200.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.100
	E101- 1- 1	MOBILIZATION	LO	5.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	250.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	5,000.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	500.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	2,500.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	20.000