

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 06240926 Call Order: 003 Proposal: E6P55 District:06

Counties: DIST/ST-WIDE, MIAMI-DADE

Road Name: DISTRICTWIDE DRAINAGE PUSHBUTTON - DRAINAGE IMPROVEMENTS

Limits: Midpoint

Project(s): 45107927201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	09/26/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$640,000.00

Please read the full advertisement

Description:

This contract consists of providing an efficient and safe operation drainage system and correct any deficiencies within the problem areas as part of the District Storm Water Management System and in compliance with the NPDES program requirements in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractors' bid price will be used to calculate the total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Bidders must complete and submit the Experience in Drainage Repair (Form No. 850-070-05) with the bid as an attachment or the bid may be deemed non-responsive.

***The award will be made at the Department Advertised Estimate amount of \$640,000.00.

Call Order: 003 Proposal: E6P55

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	400.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,250.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	25.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	25.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	800.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	100.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	25.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	35.000
	0102-115-	TYPE III BARRICADE	ED	20.000
	0104- 10- 3	SEDIMENT BARRIER	LF	50.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	75.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000

Call Order: 003 Proposal: E6P55

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	50.000
	0120- 1-	REGULAR EXCAVATION	CY	1,300.000
	0120- 6-	EMBANKMENT	CY	50.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	50.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	20.000
	0160- 4-	TYPE B STABILIZATION	SY	1,750.000
	0210- 1- 1	REWORKING LIMEROCK BASE, 6"	SY	1,850.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,850.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	200.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	200.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	90.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	50.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	25.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	5.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	7.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	7.000
	0425- 1-475	INLETS, CURB, TYPE 7, PARTIAL	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-542	INLETS, DT BOT, TYPE D, >10'	EA	1.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	1.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-552	INLETS, DT BOT, TYPE E, >10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 8-	DRAINAGE STRUCTURES, MISCELLANEOUS, ADJUST	EA	1.000
	0425- 15- 56	INLET TOP, REPLACE, APRON FOR INLET TOP	EA	1.000
	0425- 16- 11	DRAINAGE MANHOLE- REPLACE TOP AND RIM	EA	2.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	300.000
	0430- 95- 1	OUTFALL BARNACLE REMOVAL, 0 - 24"	LF	200.000
	0430- 95- 2	OUTFALL BARNACLE REMOVAL, 25 - 36"	LF	200.000
	0430- 95- 3	OUTFALL BARNACLE REMOVAL, 37-48"	LF	100.000
	0430- 95- 4	OUTFALL BARNACLE REMOVAL, 49-60"	LF	50.000
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	5.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	50.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	100.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	10.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	10.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	10.000
	0430-822- 15	CLEANING & SEALING EXISTING PIPE JOINT, 15" CD	EA	10.000
	0430-822- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" CD	EA	10.000
	0430-822- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" CD	EA	10.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	25.000
	0443- 70- 5	FRENCH DRAIN, 30"	LF	40.000

Call Order: 003 Proposal: E6P55

ALT	Item	Description	Unit	Quantity
	0443- 70- 6	FRENCH DRAIN, 36"	LF	40.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	50.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	50.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	50.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	10.000
	0527- 2-	DETECTABLE WARNINGS	SF	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	20.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	10.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	150.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	100.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	100.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	4.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.080
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	50.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	150.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	100.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	100.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	4.000
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C -30 SKIP OR 3-9 LANE DROP	GM	0.080
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	8.000
	E110- 2-	CLEARING & GRUBBING	AC	0.500
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	7.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	2.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	2.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	5.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	600.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	200.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	200.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	100.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	200.000
	E711- 3- 1	PAVEMENT MESSAGES (THERMOPLASTIC)	SF	50.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	1,000.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	250.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	1,000.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	125.000

Call Order: 003 Proposal: E6P55

ALT	Item	Description	Unit	Quantity
	E999- 3- 2	HYDRAULIC PUMP, 6"	HR	20.000