

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

|                           |                                                       |                            |                 |             |
|---------------------------|-------------------------------------------------------|----------------------------|-----------------|-------------|
| Letting:                  | 06250828                                              | Call Order: 001            | Proposal: E6P24 | District:06 |
| Counties:                 | MIAMI-DADE                                            |                            |                 |             |
| Road Name:                | SR 9A/I-95 NB FLYOVR RMP OVR NW17&NW20 ST-B-REP/REHAB |                            |                 |             |
| Limits:                   | 87270223                                              |                            |                 |             |
| Project(s):               | 44619315201(*)                                        | Federal Aid No: N/A        |                 |             |
| Total Roadway Length:     | 0.348 Miles                                           | Contract Days:             | 300             |             |
| Total Bridge Length:      | 0.348 Miles                                           | Letting Date:              | 08/28/25        |             |
| Total Proposal Length:    | 0.696 Miles                                           | Contract Execution Days:   | 10              |             |
|                           |                                                       | Special Start Date:        | N/A             |             |
|                           |                                                       | Aquis/Flexible Start Time: | 60              |             |
| Proposal Budget Estimate: | \$3,190,907.00                                        |                            |                 |             |

Please read the full advertisement

**Description:**

The improvement under this Contract consists of Bridge-Repair/Rehabilitation along SR 9A/I-95 NB Flyover Ramp Over NW 17 and NW 20 ST – Bridge #870727 in Miami-Dade County. Pre-qualification is required.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E6P24**

| ALT                            | Item         | Description                                                              | Unit | Quantity   |
|--------------------------------|--------------|--------------------------------------------------------------------------|------|------------|
| <b>Section 0001 Structures</b> |              |                                                                          |      |            |
|                                | 0401- 70- 3  | RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC                    | CF   | 2.500      |
|                                | 0411- 1-     | EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB                     | GA   | 1.000      |
|                                | 0411- 2-     | CRACKS INJECT & SEAL- STRUCTURES REHAB                                   | LF   | 155.000    |
|                                | 0413-149-    | PENETRANT SEALER                                                         | GA   | 53.000     |
|                                | 0413-154-    | CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES | SF   | 5,270.000  |
|                                | 0561- 1-     | COATING EXISTING STRUCTURAL STEEL (44619315201 870724)                   | LS   | 1.000      |
|                                | 0561- 2-     | COATING EXISTING STRUCTURAL STEEL                                        | SF   | 7,214.000  |
| <b>Section 0002 Roadway</b>    |              |                                                                          |      |            |
|                                | 0101- 1-     | MOBILIZATION (44619315201)                                               | LS   | 1.000      |
|                                | 0102- 1-     | MAINTENANCE OF TRAFFIC (44619315201)                                     | LS   | 1.000      |
|                                | 0102- 14-    | TRAFFIC CONTROL OFFICER                                                  | HR   | 288.000    |
|                                | 0102- 60-    | WORK ZONE SIGN                                                           | ED   | 1,234.000  |
|                                | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                   | ED   | 41,963.000 |
|                                | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)   | FD   | 216.000    |
|                                | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                              | ED   | 328.000    |
|                                | 0102-115-    | TYPE III BARRICADE                                                       | ED   | 42.000     |
|                                | 0102-913- 21 | REMOVABLE TAPE, WHITE, SOLID 6"                                          | GM   | 1.161      |
|                                | 0102-913- 31 | REMOVABLE TAPE, YELLOW, SOLID, 6"                                        | GM   | 0.697      |
|                                | 0104- 18-    | INLET PROTECTION SYSTEM                                                  | EA   | 17.000     |
|                                | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                           | EA   | 281.000    |
|                                | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44619315201)                     | LS   | 1.000      |
| <b>Section 0003 Signing</b>    |              |                                                                          |      |            |
|                                | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                           | EA   | 93.000     |
|                                | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES                    | GM   | 0.348      |
|                                | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES                   | GM   | 0.349      |