

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	06251120	Call Order: 006	Proposal: E6Q08-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	CONCRETE INSTALLATION - ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	42823567201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	11/20/25	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

Description:

This contract consists of construction, reconstruction and removal of concrete sidewalks, driveways, curb cut ramps, curb & gutter, and special curb and gutter on various arterial state roads in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of the Letting, the Engineer will issue a Work Document. This Work Document will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Department Advertised Estimate amount of \$400,000.00

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 006 Proposal: E6Q08-R0				
ALT	Item	Description	Unit	Quantity
Section 0001 CONCRETE SIDEWALK REPAIR (SY)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	250.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.500
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,451.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	50.000
	0120- 6-	EMBANKMENT	CY	50.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	10.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	100.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	25.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F (Colored Concrete)	LF	25.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	25.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE (Colored Concrete)	LF	25.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	50.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	20.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	50.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,555.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK (Colored Concrete)	SY	300.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	300.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK (Colored Concrete)	SY	200.000
	0527- 2-	DETECTABLE WARNINGS	SF	150.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	5.000
	E534- 72- 1	SOUND/NOISE BARRIER PANELS, F&I, REPLACE	SF	5.000
	E575- 1-	SODDING	SY	300.000