

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	06250925	Call Order: 001	Proposal: E6P26	District:06
Counties:	MONROE			
Road Name:	SR5 OVER OHIO BAHIA HONDA CHNNEL BRG 900105 BRG-REPAIR/REHAB			
Limits:	90030000			
Project(s):	44775315201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.210 Miles	Contract Days:	420	
Total Bridge Length:	0.210 Miles	Letting Date:	09/25/25	
Total Proposal Length:	0.420 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60	
Proposal Budget Estimate:	\$2,664,620.00			

Please read the full advertisement

Description:

The improvements under this contract consist of bridge repair/rehabilitation along SR5/Overseas Highway over Bahia Honda Channel Bridge 900105 in Monroe County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E6P26

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 60- 2	CATHODIC PROTECTION - ELECTRICAL WORK, DC POWER SOURCE ASSEMBLY (44775315201 900105)	LS	1.000
	0400- 60- 3	CATHODIC PROTECTION - ELECTRICAL WORK, CONDUIT, WIRING, AND ACCESSORIES (44775315201 900105)	LS	1.000
	0400- 60- 4	CATHODIC PROTECTION - ELECTRICAL WORK, EQUIPMENT & INSTRUMENTATION (44775315201 900105)	LS	1.000
	0400-142- 7	CATHODIC PROTECTION SYSTEM, TITANIUM MESH	SF	2,002.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	258.900
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	10.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	736.000
	0413-149-	PENETRANT SEALER	GA	99.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	15,230.000
	0450- 83- 1	BEAM REPAIR, STRAND SPLICES	EA	26.000
	0457- 2-232	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, GREATER THAN 30.", IMPRESSED CURRENT	LF	182.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	88.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	39.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44775315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44775315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,560.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	22,680.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	868.000
	0102-115-	TYPE III BARRICADE	ED	1,680.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44775315201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	52.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.419
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.230
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.174