

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	06250925	Call Order: 003	Proposal: E6P76	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 5/US-1/S DIXIE HIGHWAY AT SW 37 AVE-TRAFFIC OPS IMPROV			
Limits:	87030000			
Project(s):	44772315201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.314 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	09/25/25	
Total Proposal Length:	0.314 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120	
Proposal Budget Estimate:	\$1,285,125.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Traffic Operations improvement US-1/South Dixie Highway at SW 37 Avenue in Miami-Dade County. Pre-qualification is required.

Call Order: 003 Proposal: E6P76

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44772315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44772315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	540.000
	0102- 60-	WORK ZONE SIGN	ED	3,060.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,100.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,238.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	776.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	180.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	4.670
	0107- 2-	MOWING	AC	0.900
	0110- 1- 1	CLEARING & GRUBBING (44772315201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	431.000
	0110- 21-	TREE PROTECTION BARRIER	LF	342.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44772315201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	550.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	439.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,960.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	38.000

Call Order: 003 Proposal: E6P76

ALT	Item	Description	Unit	Quantity
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	364.500
	0425- 5-	MANHOLE, ADJUST	EA	3.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	111.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	103.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	101.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	19.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	118.000
	0527- 2-	DETECTABLE WARNINGS	SF	60.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	72.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	97.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.045
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	219.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	56.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	3.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.125
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44772315201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	4.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	2.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	105.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44772315201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	768.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	16.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	195.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	13.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	5.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.025
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	607.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.285
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.010

Call Order: 003 Proposal: E6P76

ALT	Item	Description	Unit	Quantity
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.029
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.232
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	445.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	180.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	27.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	5.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	7.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000
Section 0004 Landscape / Peripheral				
	0581- 1-271	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, <14.0' OF CLEAR TRUNK	EA	5.000
	0581- 1-272	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	2.000
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (44772315201)	LS	1.000