

**BID SOLICITATION NOTICE – District 6**  
**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**CONSTRUCTION AND MAINTENANCE PROGRAMS**  
District Six, Adam Leigh Cann Building  
1000 NW 111 Avenue Procurement Office, Room 6202-B  
Miami, FL 33172

Miami, FL  
December 18, 2025  
Advertisement No. 1

All bids must be completed using **Project Bids** software available on the Bid Express website at <https://bidx.com/fl/main>

Unless otherwise stipulated in the proposal description, bids for all projects listed in this Bid Solicitation Notice must be submitted using Bid Express only. No other means of submission of bids will be accepted. Please visit the Contracts Administration Website at: <https://www.fdot.gov/contracts> for more information on Bid Express. Submitting bids through Bid Express requires a Digital ID. To obtain a Digital ID, please contact Bid Express at <http://www.bidx.com>. Allow up to 6 days to complete the Digital ID registration.

Bids for the projects in this Bid Solicitation Notice will be accepted by Bid Express until 11:00 AM Local Time on Thursday, January 29, 2026.

Bid totals for each bid submitted will be read aloud for those present and will be available at 11:00 AM January 29, 2026 in the above referenced location.. Anyone needing special accommodations under the Americans with Disabilities Act of 1990 should send an e-mail to: [contracts.admin@dot.state.fl.us](mailto:contracts.admin@dot.state.fl.us) or call telephone number (305)470-5457. Special accommodation requests under the Americans with Disabilities Act should be made at least seven days prior to the public meeting. Bidders may obtain preliminary bid results at: [Select District](#), select district then click on appropriate date.

**DEADLINE FOR PROPOSALS AND PROPOSAL HOLDERS LIST**

The deadline for obtaining bid packages shall be 24 hours prior to the scheduled letting date and time. A list of plan holders may be obtained by visiting the District Contracts Administration website at: [www.fdot.gov/contracts/d6](http://www.fdot.gov/contracts/d6), click “[Letting and Project Information](#)” and select letting date from the Lettings Menu.

**-----NOTE-----**

**Proposals will not be issued after 11:00 AM Local Time on Wednesday, January 28, 2026 .**

<b>Document Ordering Information</b>
Orders for documents are placed using the Contract Proposal Processing Online Ordering System at <a href="http://CPP.fdot.gov">CPP.fdot.gov</a> . There is no charge for ordering/downloading documents. Online Ordering is available Monday through Friday from 6 AM. to 9 PM. and Saturday from 6 AM. to 7 PM.
<b>To Place An Order</b>
<ul style="list-style-type: none"><li>A current State of Florida Vendor Number is required prior to first-time registration; please visit <a href="https://vendor.myfloridamarketplace.com">https://vendor.myfloridamarketplace.com</a> for more information. Please allow 24 to 48 hours for receipt of a new vendor number.</li></ul>
Prior to placing orders, an individual shall register and establish an Internet Subscriber Account with the Department of Transportation at <a href="http://CPP.fdot.gov">CPP.fdot.gov</a> . Please allow 48 to 72 hours (excluding weekends and holidays) for the registration and approval.

## **PREQUALIFICATION**

Contractors must have a current certificate of qualification in accordance with Florida Statute 337.14(1) and Rule Chapter 14-22, Florida Administrative Code, on the date of the letting to bid on construction projects over \$250,000.00 as established by the Department's budget. Maintenance contracts do not require a contractor to have a certificate of qualification, unless stipulated in the project description and specifications. If deemed necessary by the Department, certain maintenance contracts will contain specific requirements for maintenance contractor eligibility.

## **PREQUALIFIED CONTRACTORS CURRENT CAPACITY**

In order for the Department to have the information required to determine a prequalified bidder's Current Capacity, it is necessary that the prequalified contractor certify the total dollar amount of all work the contractor has underway. This certification shall be accomplished electronically by submitting the Certification of Work Underway (Online Web Application) [https://www.fdot.gov/contracts/PreQual\\_Info/prequalified.shtm](https://www.fdot.gov/contracts/PreQual_Info/prequalified.shtm) to the Department every 30 calendar days.

## **CONFLICT OF INTEREST**

A contractor who performs a constructability review on a design contract or who participates in a value engineering study workshop or cost risk analysis workshop, is prohibited from bidding on the construction of that contract.

## **SCRUTINIZED COMPANIES**

A company that is on the Scrutinized Companies with Activities in Sudan List, is on the Scrutinized Companies with Activities in the Iran Petroleum Energy Sector List, or is engaged in business operations in Syria, may not bid on, submit a proposal for, or enter into a contract with an agency or local government entity for goods or services of \$1 million or more.

A company that is on the Scrutinized Companies that Boycott Israel List or is engaged in a boycott of Israel may not bid on, submit a proposal for, or enter into a contract with an agency or local government entity for goods or services.

## **BID REJECTION**

Bidders are hereby notified that all bids on any of the following projects are likely to be rejected if the lowest responsive bid received exceeds the engineer's estimate by more than ten percent (10%). In the event any of the bids are rejected for this reason, the project may be deferred for re-advertising. In addition, award of all federally funded projects will be subject to Federal Highway Administration concurrence.

## **PROTEST RIGHTS**

Pursuant to Section 120.57, Florida Statutes, any person adversely affected by a **bid solicitation** shall file both a notice of protest and bond within 72 hours after posting of the Bid Solicitation Notice and shall file a formal written protest within ten days after filing the notice of protest. Any person who files a notice of protest as to a bid solicitation pursuant to this rule shall post with the Department, at the time of filing the notice of protest, a bond payable to the Department in the following amounts: For an action protesting a bid solicitation that requires qualification of bidders, the bond shall be \$5,000. For an action protesting a bid solicitation for which bidders are not required to be prequalified by the Department to be eligible to bid, the bond shall be \$2,500. The required notice of protest, bond and formal protest must each be timely filed with the Clerk of Agency Proceedings, Florida Department of Transportation, Mail Station 58, Room 550, 605 Suwannee Street, Tallahassee, Florida 32399-0458, FAX (850) 414-5264. Failure to file a protest within the time prescribed in Section 120.57(3), F.S., or failure to post the bond or other security required by law within the time allowed for the filing a bond shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

Pursuant to Section 120.57, Florida Statutes, any person adversely affected by a **bid rejection or contract award** shall file both a notice of protest and bond within 72 hours after the posting of the Summary of Bids. If notice of intended decision is given by certified mail or express delivery, the adversely affected person must file both the notice of protest and bond within 72 hours after receipt of the notice of intent. A formal written protest must be filed within ten days after filing the notice of protest. Any person who files a notice of protest as to a bid rejection or contract award pursuant to this rule shall post with the Department, at the time of filing the notice of protest, a bond payable to the Department in the following amounts: For an action protesting a bid rejection or contract award that requires qualification of bidders, the Bond shall be equal to one percent of the lowest bid submitted or \$5,000, whichever is greater. For an action protesting a bid rejection or contract award for which bidders are not required to be prequalified by the Department to be eligible to bid,

the bond shall be \$2,500. The required notice of protest, bond, and formal protest must each be timely filed with the Clerk of Agency Proceedings, Florida Department of Transportation, Mail Station 58, Room 550, 605 Suwannee Street, Tallahassee, Florida 32399-0458, FAX (850) 414-5264. Failure to file a protest within the time prescribed in Section 120.57(3), Florida Statutes, shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

A protest is not timely filed unless the notice of protest, bond, and the formal protest are each received by the Clerk of Agency Proceedings within the required time limits. A protest which is filed prematurely will be deemed abandoned unless timely renewed.

Interested parties can visit our Internet web site at <https://www.fdot.gov/contracts/>. Information regarding projects posted with the Clerk of Agency Proceedings, Proposal holders, Plan and Special Provisions holders, preliminary letting results, and other noteworthy information is provided on this website.

### **IDENTICAL BIDS**

After consideration in accordance with Article 3-1 of the Standard Specifications for Road and Bridge Construction, or as amended by the project Specifications Package or any Supplemental Specifications Packages, if it is determined that multiple responsive bidders submit identical proposals (bids), the Department will determine the order in which proposals are to be considered for Contract award by means of a random selection: coin toss or drawing of lots. The method used to determine the order in which proposals are to be considered for Contract award shall be announced at the beginning of the public meeting held for the purpose described herein.

### **INSURANCE**

The successful bidder shall submit current general liability insurance and workman's compensation insurance certificates for the duration of the contract in the dollar amounts and manner specified in the most current edition of the Department's Standard Specifications for Road and Bridge Construction. Insurance companies must be authorized to do business in the State of Florida. Proof of such insurance shall be filed with the District Contracts and Procurement Office before the contract can be executed. BE SURE THAT THE CONTRACT NUMBER IS ON EACH INSURANCE CERTIFICATE.

### **ADDENDA**

No negotiations, decisions, or actions will be initiated or executed by a potential bidder as a result of any oral discussion with a State employee. Only those communications which are in writing from the Department will be considered as a duly authorized expression on behalf of the Department. Notices of changes (addenda) will be posted on the Districts Contracts Administration website at: [www.fdot.gov/contracts/d6](http://www.fdot.gov/contracts/d6), click "Letting and Project Information" and select letting date from the Lettings Menu. It is the responsibility of all potential bidders to monitor this site for any changing information prior to submitting their bid. **All addenda will be acknowledged by signature and subsequent submission of addenda with the bid when so stated in the addenda.**

### **BID QUESTIONS**

Direct questions regarding the advertised projects by posting them to the Department website at the following URL address: <https://bqa.fdot.gov>.

### **PROPOSAL GUARANTY**

For bids over \$150,000.00, the standard proposal guaranty of 5% of the bid will be required, unless otherwise stipulated in the proposal advertisement. A Proposal Guaranty of not less than five percent (5%) of the total actual bid in the form of either a certified check, cashier's check, trust company treasurer's check, bank draft of any national or state bank, or a Surety Proposal Guaranty made payable to the Florida Department of Transportation must be received for each bid in excess of **\$150,000.00**. A check or draft in an amount less than five percent (5%) of the actual bid will invalidate the bid. The guaranty amount shall include all bid items except construction days for A+B bidding and lane closure for Lane Rental Bidding. Proposal Guaranty shall substantially conform to DOT Form 375-020-09. Surety2000 or Tinubu Surety Solution electronic Proposal Guaranty submittal may be used in conjunction with Bid Express internet bid submittal. For more information, please visit <https://www.surety2000.com> for Surety2000 or <https://www.tinubu.com> for Tinubu Surety Solution. Paper Proposal Guaranty will also be accepted for bids submitted through Bid Express provided they are received prior to the deadline for receiving bids, by the location(s) identified in this Bid Solicitation Notice. If an electronic

proposal guaranty is not being submitted, the bidder must submit an original proposal guaranty. (A fax or a copy sent as an attachment will not be accepted.)

### **EXECUTION OF CONTRACT**

Pursuant to Subsections 3-6 and 3-7 of the Standard Specifications, the successful bidder shall execute the necessary contract documents and return the agreement along with a satisfactory Performance and Payment Bond within ten (10) Calendar days of award, excluding Saturdays, Sundays, and state holidays, unless noted otherwise in the project specifications. A 100% Payment and Performance Bond will be required for all projects unless noted otherwise in the project specifications. All work is to be done in accordance with the Plans, special Provisions of the State of Florida Department of Transportation.

Prior to execution of the contract with the Department, **a corporation must show proof that it is authorized to do business in the State of Florida.** Florida corporations should provide a copy of the certificate of Incorporation and foreign corporations should provide a copy of Certificate of Authority from the Florida Department of State.

**Important Note:** Actual commitment and final execution of the contract is contingent upon an approved legislative budget and funds availability.

### **DEBARMENT/SUSPENSION**

All bids submitted to the Department shall include a statement that by signing and submitting this proposal, the bidder certifies that no principal (which includes officers, directors or executives) is presently debarred, suspended, proposed for debarment, declared ineligible or voluntarily excluded from participation in this transaction by any federal department or agency.

### **MANDATORY PRE-BID CONFERENCE**

For projects with mandatory Pre-Bid Meeting, proposals (BIDDING DOCUMENTS) will be issued only to the attendees of the meeting. Prospective bidders ordering bidding documents prior to the Pre-Bid Meeting will be given access to download the bidding documents within 24 hours after the Pre-Bid Meeting. Those prospective bidders ordering the documents after the Pre-Bid Meeting will need to contact the office advertising the project to confirm attendance and receive access to download the bidding documents. Please contact the office at least two working days prior to the deadline for obtaining bidding documents to allow time for processing.

### **LATE ARRIVALS TO MANDATORY PRE-BID MEETINGS**

All bidders must be present and signed in prior to the start of the mandatory pre-bid meeting. Anyone not signed in at the commencement of the meeting will be considered late and will not be allowed to bid on the project.

### **FIRST TIME BIDDERS**

Bidders bidding for the first time with the Department can access the New Bidder's Orientation document at:

[https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/contracts/new-bidders-orientation.pdf?sfvrsn=aef131ae\\_2](https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/contracts/new-bidders-orientation.pdf?sfvrsn=aef131ae_2)

### **POSTING NOTICE**

The bid tabulation and intent to award will be posted on February 17, 2026 or March 03, 2026 at [www.fdot.gov/contracts/d6](http://www.fdot.gov/contracts/d6), click the "Letting and Project Information" and select letting date from the Listings Menu. The posting provides notice of the Department's intent to award a contract or reject all bids. The Department's Notice of Intent regarding a project will be posted on only one of the alternate posting dates. Bidders are solely responsible for timely monitoring or otherwise verifying on which of the specified alternate posting dates the posting of award or rejection of all bids actually occurs.

If the posting dates are revised, all bidders for the subject project will be notified.



### **AFFIRMATIVE ACTION (EQUAL EMPLOYMENT OPPORTUNITY)**

The Florida Department of Transportation (hereinafter referred to as the "Department"), in accordance with **Title VI of the Civil Rights Act of 1964, 42 USC 2000d to 2000d-4 and related authorities, Title 49, Code of Federal Regulations, U.S. Department of Transportation, Subtitle A, Office of the Secretary, Part 21**, Nondiscrimination in Federally-assisted programs of the U.S. Department of Transportation issued pursuant to such Act, hereby notifies all bidders that the Department will affirmatively insure that in any contract entered into pursuant to this advertisement, minority and disadvantaged business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the basis of race, color, national origin, or sex in consideration for an award. Further, it is the policy of the Department to not discriminate against bidders on the grounds of race, color, national origin, religion, sex, age, or disability/handicap in consideration for an award.

### **MINIMUM WAGE**

The minimum wage for all hours worked in Florida is available at <https://www.floridajobs.org>.

### **EMAIL SUBSCRIPTION LIST**

To get on the e-mail subscription list, go to <http://fdotwp1.dot.state.fl.us/reportsubscriptions/> and fill out the necessary information to "Subscribe". To obtain information concerning other districts, go to <https://www.fdot.gov/contracts/district-offices/distco.shtm>.

### **NOTICE TO ALL BIDDERS**

To report bid rigging activities call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 A.M. to 5:00 P.M. Local Time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

By submitting a bid, the contractor/consultant/vendor agrees to comply with section 20.055(5) Florida Statute, and to incorporate in all subcontracts the obligation to comply with section 20.055(5) Florida Statute.

**Florida Department of Transportation**  
**Notice to Contractors Index**

---

Published: December 18, 2025

Letting ID: 06260129

Please use the following proposal ID and the letting ID when ordering plans/proposal or specifications for the January 29, 2026 letting.

Page Number	Proposal Id	Proposal Notes	Fin Proj Numbers	County
7	E6P72		45344315201(*)	MIAMI-DADE
8	E6P78		44644425201(*)	DIST/ST-WIDE, MIAMI-DADE, MONROE
18	E6P84		44626355201(*)	MIAMI-DADE
25	E6P99-R0		44424847201(*)	MIAMI-DADE
26	E6Q02-R0		44429837201(*)	MIAMI-DADE
27	E6Q09		45785417201(*)	MIAMI-DADE
29	E6Q10-R0		45789517201(*)	MIAMI-DADE
30	E6Q11-R0		45790217201(*)	MIAMI-DADE
32	E6Q14		45794217201(*)	MIAMI-DADE

**Proposal Note Codes:**

*Note: (\*) indicates lead project*

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting: 06260129      Call Order: 001      Proposal: E6P72      District:06  
Counties: MIAMI-DADE  
Road Name: SR 27/OKCBEE RD FRM BRWRD CNTY LINE TO W OF HEFT - LNDSCPING  
Limits: 87090000  
Project(s): 45344315201(\*)      Federal Aid No: N/A  
Total Roadway Length: 4.591 Miles      Contract Days: 1000  
Total Bridge Length: 0.000 Miles      Letting Date: 01/29/26  
Total Proposal Length: 4.591 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 30  
Proposal Budget Estimate: \$1,807,564.00

Please read the full advertisement

Description:

This Contract consists of landscape installation along SR25/US27/Okeechobee Road from Broward County Line to West of Heft in Miami-Dade County.

Experience Form 850-070-09 Experience in Landscaping must be submitted with your bid.

**Call Order: 001    Proposal: E6P72**

---

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Landscape / Peripheral</b>				
	0999- 2-	LUMP SUM CONTRACT, ALTERNATIVE BIDDING (45344315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45344315201)	LS	1.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	06260129	Call Order: 002	Proposal: E6P78	District:06
Counties:	DIST/ST-WIDE, MIAMI-DADE, MONROE			
Road Name:	DISTRICTWIDE PUSHBUTTON LANDSCAPING			
Limits:	Midpoint			
Project(s):	44644425201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	1100	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	
Proposal Budget Estimate:	\$944,954.00			

Please read the full advertisement

**Description:**

The work under this Contract consists of Districtwide Landscape Pushbutton Contract.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Experience Form 850-070-09 Experience in Landscaping must be submitted with your bid.

Award will be made at the Department Advertised Estimate Amount of \$944,954.00.

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0102- 60-	WORK ZONE SIGN	ED	400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	250.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	25.000
	0102-115-	TYPE III BARRICADE	ED	100.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	2,000.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	25.000
	0107- 1-	LITTER REMOVAL	AC	20.000
	0107- 2-	MOWING	AC	20.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	100.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	50.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	100.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	30.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	50.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	100.000
	0550- 10-228	FENCING, TYPE B, 5.1-6.0, RESET EXISTING	LF	100.000
	0550- 60-211	FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING	EA	3.000
<b>Section 0002 Landscape / Peripheral</b>				
	0110- 21-	TREE PROTECTION BARRIER	LF	500.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	40.000
	0570- 1-130	PERFORMANCE TURF, SODDING- ST AUGUSTINE FLORATAM (MIAMI-DADE COUNTY)	SY	1,000.000
	0570- 1-130	PERFORMANCE TURF, SODDING- ST AUGUSTINE FLORATAM (MONROE COUNTY)	SY	500.000
	0570- 1-131	PERFORMANCE TURF, SEEDING- BAHIA 'ARGENTINE'	SY	1,500.000
	0570- 1-132	PERFORMANCE TURF, SEEDING- COMMON BERMUDA	SY	100.000
	0570- 1-133	PERFORMANCE TURF, SEEDING- ZOYSIA COMPADRE	SY	100.000
	0570- 1-134	PERFORMANCE TURF, SODDING- BAHIA 'ARGENTINE' (MIAMI-DADE COUNTY)	SY	2,000.000
	0570- 1-134	PERFORMANCE TURF, SODDING- BAHIA 'ARGENTINE' (MONROE COUNTY)	SY	1,000.000
	0570- 1-135	PERFORMANCE TURF, SODDING- COMMON BERMUDA	SY	500.000
	0570- 1-136	PERFORMANCE TURF, SODDING- SEASHORE PASPALUM	SY	500.000
	0570- 1-137	PERFORMANCE TURF, SODDING- ZOYSIA EMPIRE	SY	500.000
	0570- 1-138	FERTILIZER- SLOW RELEASE FOR TURF	TN	1.000
	0570- 1-139	FERTILIZER- SLOW RELEASE FOR TREES	SY	25,000.000
	0570- 1-140	FERTILIZER- SLOW RELEASE FOR PALMS	SY	25,000.000
	0570- 1-141	FERTILIZER- SLOW RELEASE FOR SHRUBS	SY	50,000.000
	0580- 4-102	LANDSCAPE- PALMS, SILVER BISMARCK PALM BISMARCKIA NOBILIS 'SILVER' - 5-8' CLEAR TRUNK	EA	25.000
	0580- 4-103	LANDSCAPE- PALMS, SILVER BISMARCK PALM BISMARCKIA NOBILIS 'SILVER' - 9-12' CLEAR TRUNK	EA	50.000
	0580- 4-113	LANDSCAPE- PALMS, PAUROTIS PALM ACOELORRHAPHE WRIGHTII, 11-14', OVERALL HEIGHT	EA	20.000
	0580- 4-142	LANDSCAPE- PALMS, FLORIDA SILVER PALM COCCOTHRINAX ARGENTATA, 4-6', OVERALL HEIGHT	EA	10.000
	0580- 4-172	LANDSCAPE- PALMS, RED LATAN PALM LATANIA LONTARIOIDES, 8-10', OVERALL HEIGHT	EA	10.000
	0580- 4-183	LANDSCAPE- PALMS, AUSTRALIAN FAN PALM LIVISTONA AUSTRALIS, 11-14', OVERALL HEIGHT	EA	10.000
	0580- 4-213	LANDSCAPE- PALMS, MEDJOOL DATE PALM PHOENIX DACTYLIFERA 'MEDJOOL', 9-12', CLEAR TRUNK	EA	10.000
	0580- 4-215	LANDSCAPE- PALMS, MEDJOOL DATE PALM PHOENIX DACTYLIFERA 'MEDJOOL', 16-20', CLEAR TRUNK	EA	10.000
	0580- 4-233	LANDSCAPE- PALMS, WILD DATE PALM/SYLVESTER PHOENIX SYLVESTRIS, 9-12', CLEAR TRUNK	EA	25.000
	0580- 4-234	LANDSCAPE- PALMS, WILD DATE PALM/SYLVESTER PHOENIX SYLVESTRIS, 13-15', CLEAR TRUNK	EA	25.000
	0580- 4-244	LANDSCAPE- PALMS, ALEXANDER PALM SINGLE PTYCHOSPERMA ELEGANS, 15-18', OVERALL HEIGHT	EA	100.000



**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 4-245	LANDSCAPE- PALMS, ALEXANDER PALM SINGLE PTYCHOSPERMA ELEGANS, 19-24', OVERALL HEIGHT	EA	50.000
	0580- 4-284	LANDSCAPE- PALMS, FLORIDA ROYAL PALM ROYSTONEA ELATA, 13-16', GREY WOOD	EA	100.000
	0580- 4-285	LANDSCAPE- PALMS, FLORIDA ROYAL PALM ROYSTONEA ELATA, 17-20', GREY WOOD	EA	75.000
	0580- 4-286	LANDSCAPE- PALMS, FLORIDA ROYAL PALM ROYSTONEA ELATA, 21-24', GREY WOOD	EA	50.000
	0580- 4-291	LANDSCAPE- PALMS, THATCH PALM SINGLE THRINAX RADIATA, UP TO 8', OVERALL HEIGHT	EA	50.000
	0580- 4-304	LANDSCAPE- PALMS, MONTGOMERY PALM SINGLE VEITCHIA MONTGOMERYANA, 15-18', OVERALL HEIGHT	EA	75.000
	0580- 4-305	LANDSCAPE- PALMS, MONTGOMERY PALM SINGLE VEITCHIA MONTGOMERYANA, 19-24', OVERALL HEIGHT	EA	25.000
	0580- 4-345	LANDSCAPE- PALMS, SABAL PALMETTO SABAL PALMETTO, 16-20' CLEAR TRUNK	EA	150.000
	0580- 4-346	LANDSCAPE- PALMS, SABAL PALMETTO SABAL PALMETTO, 21-24' CLEAR TRUNK	EA	75.000
	0580- 4-347	LANDSCAPE- PALMS, SABAL PALMETTO SABAL PALMETTO, 25-30' CLEAR TRUNK	EA	50.000
	0580- 4-352	LANDSCAPE- PALMS, ARECA PALM DYPsis LUTESCENS, 8-10', OVERALL HEIGHT	EA	10.000
	0580- 4-353	LANDSCAPE- PALMS, ARECA PALM DYPsis LUTESCENS, 11-14', OVERALL HEIGHT	EA	10.000
	0580- 4-361	LANDSCAPE- PALMS, CANARY ISLAND DATE PALM PHOENIX CANARIENSIS, UP TO 4', CLEAR TRUNK	EA	5.000
	0580- 4-362	LANDSCAPE- PALMS, CANARY ISLAND DATE PALM PHOENIX CANARIENSIS, 5-8', CLEAR TRUNK	EA	5.000
	0580- 4-364	LANDSCAPE- PALMS, CANARY ISLAND DATE PALM PHOENIX CANARIENSIS, 13-15', CLEAR TRUNK	EA	5.000
	0580- 4-374	LANDSCAPE- PALMS, REGENERATED SABAL PALMETTO SABAL PALMETTO, 13-15' CLEAR TRUNK	EA	100.000
	0580- 4-377	LANDSCAPE- PALMS, REGENERATED SABAL PALMETTO SABAL PALMETTO, 25-30' CLEAR TRUNK	EA	100.000
	0580- 4-404	LANDSCAPE- PALMS, SENEGAL DATE PALM, PHOENIX RECLINATA, 15-18' OVERALL HEIGHT	EA	5.000
	0580- 4-483	LANDSCAPE- PALMS, ADONIDIA MERRILLII, 11-14', OVERALL HEIGHT	EA	25.000
	0580- 4-492	LANDSCAPE- PALMS, CARPENTARIA ACUMINATA - CARPENTARIA PALM, 9-12' CLEAR TRUNK	EA	10.000
	0580- 4-502	LANDSCAPE- PALMS, LATANIA LODDIGESII- BLUE LATIN PALM, 8-10', OVERALL HEIGHT	EA	10.000
	0580- 4-512	LANDSCAPE- PALMS, DYPsis DECARYI - TRIANGLE PALM, 8-10', OVERALL HEIGHT	EA	10.000
	0580- 4-523	LANDSCAPE- PALMS, LIVISTONA NITIDA- CARNAVON GORGE PALM, 11-14', OVERALL HEIGHT	EA	25.000
	0580- 4-533	LANDSCAPE- PALMS, COCOS NUCIFERA 'MAYPAN' 9-12' GREY WOOD	EA	10.000
	0580- 4-534	LANDSCAPE- PALMS, COCOS NUCIFERA 'MAYPAN' 13-16' GREY WOOD	EA	10.000
	0580- 4-542	LANDSCAPE- PALMS, LEUCOTHRINAX MORRISII, KEYS THATCH PALM, 4-6' OVERALL HEIGHT	EA	25.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 4-557	LANDSCAPE- PALMS,ROYSTONEA REGIA- ROYAL PALM, 25-30' GREY WOOD	EA	30.000
	0580- 5-132	LANDSCAPE- TREES, CRAPE MYRTLE STANDARD/SINGLE LAGERSTROEMIA INDICA 'STANDARD', 8-10' OVERALL HEIGHT	EA	25.000
	0580- 5-142	LANDSCAPE- TREES, CRAPE MYRTLE MULTI LAGERSTROEMIA INDICA 'MULTI', 8-10' OVERALL HEIGHT	EA	25.000
	0580- 5-152	LANDSCAPE- TREES, QUEEN'S CRAPE MYRTLE STANDARD/SINGLE, LAGERSTROEMIA SPECIOSA 'STANDARD', 8-10' OVERALL HEIGHT	EA	15.000
	0580- 5-173	LANDSCAPE- TREES, BALD CYPRESS TAXODIUM DISTICHUM , 11-14' OVERALL HEIGHT	EA	25.000
	0580- 5-174	LANDSCAPE- TREES, BALD CYPRESS TAXODIUM DISTICHUM, 15-18' OVERALL HEIGHT	EA	25.000
	0580- 5-184	LANDSCAPE- TREES, GUMBO LIMBO BURSERIA SIMARUBA, 15-18' OVERALL HEIGHT	EA	100.000
	0580- 5-213	LANDSCAPE- TREES, MAGNOLIA SWEET BAY MAGNOLIA VIRGINIA, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-223	LANDSCAPE- TREES, LIVE OAK QUERCUS VIRGINIANA, 11-14' OVERALL HEIGHT	EA	100.000
	0580- 5-224	LANDSCAPE- TREES, LIVE OAK QUERCUS VIRGINIANA, 15-18' OVERALL HEIGHT	EA	75.000
	0580- 5-225	LANDSCAPE- TREES, LIVE OAK QUERCUS VIRGINIANA, 19-24' OVERALL HEIGHT	EA	50.000
	0580- 5-226	LANDSCAPE- TREES, LIVE OAK QUERCUS VIRGINIANA, 25-30' OVERALL HEIGHT	EA	25.000
	0580- 5-231	LANDSCAPE- TREES, SOUTH FLORIDA SLASH PINE PINUS ELLIOTII DENSE, UP TO 8" OVERALL HEIGHT	EA	75.000
	0580- 5-233	LANDSCAPE- TREES, SOUTH FLORIDA SLASH PINE PINUS ELLIOTII DENSE, 11-14' OVERALL HEIGHT	EA	50.000
	0580- 5-243	LANDSCAPE- TREES, SILVER TRUMPET TREE TABEBUIA CARAIBA, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-252	LANDSCAPE- TREES, PINK TRUMPET TREE TABEBUIA HETEROPHYLLA, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-254	LANDSCAPE- TREES, PINK TRUMPET TREE TABEBUIA HETEROPHYLLA, 15-18' OVERALL HEIGHT	EA	15.000
	0580- 5-272	LANDSCAPE- TREES, VERAWOOD BULNESIA ARBOREA, 8-10' OVERALL HEIGHT	EA	15.000
	0580- 5-282	LANDSCAPE- TREES, FLOSS SILK TREE CHORISIA SPECIOSA, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-303	LANDSCAPE- TREES, GREEN BUTTONWOOD CONOCARPUS ERECTUS, 11-14' OVERALL HEIGHT	EA	150.000
	0580- 5-313	LANDSCAPE- TREES, SILVER BUTTONWOOD CONOCARPUS ERECTUS VAR. SERICEUS, 11-14' OVERALL HEIGHT	EA	200.000
	0580- 5-323	LANDSCAPE- TREES, ROYAL POINCIANA DELONIX REGIA, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-333	LANDSCAPE- TREES, YELLOW POINCIANA/JACARANDA PELTOPHORUM DUBIUM, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-341	LANDSCAPE- TREES, FRANGIPANI TREE, BRIDAL BOUQUET, PLUMERIA PUDICA, UP TO 8' OVERALL HEIGHT	EA	10.000
	0580- 5-353	LANDSCAPE- TREES, MAHOGANY SWietenia MAHAGONI, 11-14' OVERALL HEIGHT	EA	50.000
	0580- 5-362	LANDSCAPE- TREES, PARADISE TREE SIMAROUBA GLAUCA, 8-10' OVERALL HEIGHT	EA	25.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 5-403	LANDSCAPE- TREES, HORSEFLESH MAHOGANY LYSILOMA SABICU, 11-14' OVERALL HEIGHT	EA	25.000
	0580- 5-422	LANDSCAPE- TREES, DAHOON HOLLY TREE ILEX CASSINE, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-452	LANDSCAPE- TREES, BRIDALVEIL TREE CAESALPINIA GRANDILLO, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-462	LANDSCAPE- TREES, GEIGER TREE CORDIA SEBESTENA, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-473	LANDSCAPE- TREES, PURPLE TRUMPET TREE TABEBUIA IMPETIGINOSA, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-481	LANDSCAPE- TREES, HOLLYWOOD LIGNUM VITAE GUAIAECUM SANCTUM, UP TO 8' OVERALL HEIGHT	EA	25.000
	0580- 5-493	LANDSCAPE- TREES, BLACK OLIVE BUCIDA BUCERAS, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-503	LANDSCAPE- TREES, COCCOLOBA DIVERSIFOLIA - PIGEONPLUM - 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-512	LANDSCAPE- TREES, WILLOW BUSTIC, SIDEROXYLON SALICIFOLIUM / DIPHOLIS SALICOFOLIUM, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-523	LANDSCAPE- TREES, FLORIDA FLAME RED MAPLE, ACER RUBRUM 'FLORIDA FLAME', 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-663	LANDSCAPE- TREES, JACARANDA JACARANDA MIMIOSAFOLIA, 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-692	LANDSCAPE- TREES, ANNONA GLABRA (POND APPLE)	EA	10.000
	0580- 5-702	LANDSCAPE- TREES, CLUSIA ROSEA (PITCH APPLE)	EA	35.000
	0580- 5-713	LANDSCAPE- TREES, COCCOLOBA UVIFERA - SEAGRAPE	EA	10.000
	0580- 5-722	LANDSCAPE- TREES, EUGENIA FOETIDA - SPANISH STOPPER	EA	10.000
	0580- 5-732	LANDSCAPE- TREES, SHORT LEAF FIG - FICUS CITRIFOLIA, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-742	LANDSCAPE- TREES, GUAPIRA DISCOLOR- BLOLLY , 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-752	LANDSCAPE- TREES, KRUGIODENDRON FERREUM - BLACK IRONWOOD , 8-10' OVERALL HEIGHT	EA	20.000
	0580- 5-762	LANDSCAPE- TREES, LYSILOMA LATHYRIFORMIS -WILD TAMARIND , 11-14' OVERALL HEIGHT	EA	25.000
	0580- 5-772	LANDSCAPE- TREES, PISCIDIA PISCIPULA - JAMAICAN DOGWOOD 8-10' OVERALL HEIGHT	EA	15.000
	0580- 5-783	LANDSCAPE- TREES, TAXODIUM ASCENDENS - POND CYPRESS 11-14' OVERALL HEIGHT	EA	10.000
	0580- 5-791	LANDSCAPE- TREES, ACACIA FARNESIANA - SWEET ACACIA, UP TO 8' OVERALL HEIGHT	EA	10.000
	0580- 5-802	LANDSCAPE- TREES, BAUHINIA BLAKEANA - HONG KONG ORCHID TREE, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-812	LANDSCAPE- TREES, CORDIA BOISSIERI - TEXAS OLIVE, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-822	LANDSCAPE- TREES, JATROPHA INTEGERRIMA- PEREGRINA, 8-10' OVERALL HEIGHT	EA	50.000
	0580- 5-832	LANDSCAPE- TREES, PARKINSONIA ACULEATA - JERUSALEM THORN, 8-10' OVERALL HEIGHT	EA	10.000
	0580- 5-841	LANDSCAPE- TREES, SENNA POLYPHYLLA - DESERT CASSIA, UP TO 8' OVERALL HEIGHT	EA	10.000
	0580- 5-853	LANDSCAPE- TREES, SPATHODEA CAMPANULATA- AFRICAN TULIP TREE, 11-14' OVERALL HEIGHT	EA	10.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 5-863	LANDSCAPE- TREES, TECOMA STANS- YELLOW ELDER, 11-14' OVERALL HEIGHT	EA	25.000
	0580- 6-222	LANDSCAPE- LARGE SHRUB, GREEN BUTTONWOOD- CONOCARPUS ERECTUS, 15-19 GALLON (44644425201)	EA	200.000
	0580- 6-291	LANDSCAPE- LARGE SHRUB, LICUALA GRANDIS, 7-14 GALLON CONTAINER (44644425201)	EA	20.000
	0580- 7-103	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, MUHLY GRASS MUHLENBERGIA CAPILLARIS, 3 GALLON CONTAINER	EA	200.000
	0580- 7-113	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BOSTON FERN NEPHROLEPIS EXALTATA, 3 GALLON CONTAINER	EA	100.000
	0580- 7-123	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, DWARF FAKAHATCHEE GRASS, TRIPSACUM FLORIDANA, 3 GALLON CONTAINER	EA	200.000
	0580- 7-133	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, JAMAICA CAPER CAPPARIS CYNOPHALLOPHORA, 3 GALLON CONTAINER	EA	100.000
	0580- 7-153	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SILVER BUTTONWOOD CONOCARPUS ERECTUS VAR. SERICEUS, 3 GALLON	EA	400.000
	0580- 7-163	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, HORIZONTAL COCOPLUM CHRYSOBALANUS ICACO 'HORIZONTAL', 3 GALLON	EA	300.000
	0580- 7-173	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, RED TIP COCOPLUM CHRYSOBALANUS ICACO 'RED TIP', 3 GALLON	EA	400.000
	0580- 7-183	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ACALYPHA WILKESIANA- COPPERLEAF, 3 GALLON	EA	100.000
	0580- 7-193	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, DWARF YOUNG HOLLY ILEX VOMITORIA 'SCHILLINGS', 3 GALLON	EA	100.000
	0580- 7-203	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, DWARF FIREBRUSH- HAMELIA PATENS 'COMPACTA', 3 GALLON	EA	400.000
	0580- 7-213	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, FIREBRUSH- HAMELIA PATENS, 3 GALLON	EA	400.000
	0580- 7-233	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SPANISH STOPPER- EUGENIA FOETIDA, 3 GALLON	EA	200.000
	0580- 7-253	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, GREEN ISLAND FICUS- FICUS MICROCARPA 'GREEN ISLAND', 3 GALLON	EA	200.000
	0580- 7-263	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, COONTIE ZAMIA PUMILA, 3 GALLON	EA	50.000
	0580- 7-273	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, MACHO FERN- NEPHROLEPIS FALCATA 'MACHO', 3 GALLON	EA	200.000
	0580- 7-283	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, WILD COFFEE- PSYCHOTRIA NERVOSA, 3 GALLON	EA	100.000
	0580- 7-313	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SILVER SAW PALMETTO SERENOA REPENS 'CINEREA', 3 GALLON	EA	50.000
	0580- 7-333	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SIMPSON'S STOPPER MYRCIANTHES FRAGRANS, 3 GALLON	EA	200.000
	0580- 7-373	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, MARSH GRASS/ SAND CORD GRASS, SPARTINA BAKERI, 3 GALLON	EA	200.000
	0580- 7-383	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ALLAMANDA VIOLACEA- PURPLE ALLAMANDA, 3 GALLON	EA	50.000
	0580- 7-393	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ALPINIA ZERUMBET VARIEGATE- VARIEGATED SHELLFLOWER, 3 GALLON	EA	150.000
	0580- 7-401	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ARACHIS GLABRATA- RHIZOMA PERENNIAL PEANUT, 1 GALLON	EA	100.000
	0580- 7-413	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ARDISIA ESCALLONIOIDES- MARLBERRY, 3 GALLON	EA	25.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 7-423	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BORRICHIA FRUTESCENS- SEA OXEYE, 3 GALLON	EA	25.000
	0580- 7-433	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BOUGAINVILLEA SPP, 3 GALLON	EA	25.000
	0580- 7-443	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, CALLICARPA AMERICANA-AMERICAN BEAUTYBERRY, 3 GALLON	EA	25.000
	0580- 7-453	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, RANDIA ACULEATA WHITE INDIGOBERRY, 3 GALLON	EA	25.000
	0580- 7-463	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS,CARISSA MACROCARPA- 'EMERALD BLANKET', DWARF NATAL PLUM, 3 GALLON	EA	150.000
	0580- 7-471	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, IPOMOEA PES-CAPRAE BEACH MORNING GLORY, 1 GALLON	EA	50.000
	0580- 7-483	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, CHRYSOBALANUS ICACO L- COCOPLUM 'GREEN TIP', 3 GALLON	EA	200.000
	0580- 7-493	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS,JASMINUM VOLUBILE , 3 GALLON	EA	50.000
	0580- 7-503	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, PHILODENDRON BIPINNATIFIDUM/PHILODENDRON SELLOUM- SELLOUM, 3 GALLON	EA	50.000
	0580- 7-513	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, CODIAEUM VARIEGATUM- CROTON, 3 GALLON	EA	50.000
	0580- 7-521	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, FICUS PUMILA- CREEPING FIG, 1 GALLON	EA	100.000
	0580- 7-543	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS,CRINUM AUGUSTUM- QUEEN EMMA , 3 GALLON	EA	50.000
	0580- 7-553	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, DIANELLA TASMANICA- TASMAN FLAX-LILY, 3 GALLON	EA	100.000
	0580- 7-563	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, DURANTA ERECTA, 3 GALLON	EA	100.000
	0580- 7-571	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ERNODEA LITTORALIS GOLDEN CREEPER, 1 GALLON	EA	200.000
	0580- 7-583	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SOPHORA TOMENTOSA, 3 GALLON	EA	50.000
	0580- 7-591	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, EVOLVULUS GLOMERATUS, 1 GALLON	EA	50.000
	0580- 7-603	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, NERIUM OLEANDER- OLEANDER, 3 GALLON	EA	25.000
	0580- 7-611	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, HELIANTHUS DEBILIS BEACH SUNFLOWER, 1 GALLON	EA	50.000
	0580- 7-623	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, HYMENOCALLIS LATIFOLIA SPIDER LILY, 3 GALLON	EA	50.000
	0580- 7-633	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, PLUMBAGO AURICULATA-PLUMBAGO, 3 GALLON	EA	50.000
	0580- 7-643	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, PODOCARPUS MACROPHYLLUS: PODOCARPUS, 3 GALLON	EA	50.000
	0580- 7-653	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, JATROPHA INTEGERRIMA: PEREGRINA, 3 GALLON	EA	50.000
	0580- 7-661	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, JUNIPERUS CONFERTA, SHORE JUNIPER/COMPACTA, 1 GALLON	EA	100.000
	0580- 7-673	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, TRIPSACUM DACTYLOIDES- FAKAHATCHEE GRASS, 3 GALLON	EA	400.000
	0580- 7-683	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ZAMIA FURFURACEA- CARDBOARD PLANT, 3 GALLON	EA	50.000



**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 7-703	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BOUGAINVILLEA - HELEN JOHNSON', 3 GALLON	EA	50.000
	0580- 7-713	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, CLUSIA GUTTIFERA 'NANA', 3 GALLON	EA	200.000
	0580- 7-723	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, CLUSIA GUTTIFERA, 3 GALLON	EA	250.000
	0580- 7-733	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, GREEN BUTTONWOOD CONOCARPUS ERECTUS, 3 GALLON	EA	400.000
	0580- 7-741	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, MILKWEED - BUTTERFLYWEED ASCLEPIAS TUBEROSA, 1 GALLON	EA	30.000
	0580- 7-751	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, PINK SWAMP MILKWEED ASCLEPIAS INCARNATA, 1 GALLON	EA	30.000
	0580- 7-761	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, WHITE SWAMP MILKWEED ASCLEPIAS PERENNIS, 1 GALLON	EA	30.000
	0580- 7-773	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, PINELAND CROTON CROTON LINEARIS, 3 GALLON	EA	30.000
	0580- 7-783	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BAY CEDAR SURIANA MARITIMA, 3 GALLON	EA	30.000
	0580- 7-791	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BLANKETFLOWER GAILLARDIA PULCHELLA, 1 GALLON	EA	30.000
	0580- 7-803	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, PORTERWEED STACHYTARPHETA JAMAICENSIS, 3 GALLON	EA	30.000
	0580- 7-811	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, TICKSEED COREOPSIS SPP. , 1 GALLON	EA	30.000
	0580- 7-823	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, RED MANGROVE RHIZOPHORA MANGLE, 3 GALLON	EA	30.000
	0580- 7-833	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BLACK MANGROVE AVICENNIA GERMINANS, 3 GALLON	EA	30.000
	0580- 7-843	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, WHITE MANGROVE LAGUNCULARIA RACEMOSA, 3 GALLON	EA	30.000
	0580- 7-851	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BEACH ELDER IVA IMBRICATA, 1 GALLON	EA	30.000
	0580- 7-861	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SEA LAVENDER HELIOTROPIUM GNAPHALODES, 1 GALLON	EA	30.000
	0580- 7-871	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SEA OATS UNIOLA PANICULATA, 1 GALLON	EA	30.000
	0580- 7-881	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SALTBUSH BACCHARIS ANGUSTIFOLIA, 1 GALLON	EA	30.000
	0580- 7-891	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, SEA PURSLANE SESUVIUM PORTULACASTRUM, 1 GALLON	EA	30.000
	0580- 7-903	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, WAX MYRTLE MYRICA CERIFERA, 3 GALLON	EA	75.000
	0580- 7-911	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BUTTONBUSH CEPHALANTHUS OCCIDENTALIS, 1 GALLON	EA	30.000
	0580- 7-923	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BROMELIAD AECHMEA BLANCHETIANA, 3 GALLON	EA	25.000
	0580- 7-931	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BLUSHING BROMELIAD NEOREGELIA SPP. , 1 GALLON	EA	50.000
	0580- 7-943	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, WART FERN MICROSORUM SCOLOPENDRIUM, 3 GALLON	EA	75.000
	0580- 7-953	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, BURLE MARX PHILODENDRON, 3 GALLON	EA	75.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0580- 7-963	LANDSCAPE- SMALL SHRUB/ORNAMENTAL GRASS, ROJO CONGO PHILODENDRON, 3 GALLON	EA	50.000
	0580- 8- 1	LANDSCAPE- PALM PRUNING/TRIMMING, MANUAL, LESS THAN 14' OF CLEAR TRUNK	EA	25.000
	0580- 8- 2	LANDSCAPE- PALM PRUNING/TRIMMING, MANUAL, 14' AND GEATER OF CLEAR TRUNK	EA	23.000
	0580- 8- 6	LANDSCAPE- STAKING AND GUYING EXISTING PALM	EA	20.000
	0580- 8- 10	LANDSCAPE- TREE PRUNING/TRIMMING, MANUAL, 1 TO 8" DBH	EA	35.000
	0580- 8- 11	LANDSCAPE- TREE PRUNING/TRIMMING, MANUAL, 8 TO 24" DBH	EA	35.000
	0580- 8- 12	LANDSCAPE- TREE PRUNING/TRIMMING, MANUAL, 24" AND GREATER DBH	EA	25.000
	0580- 8- 16	LANDSCAPE- STAKING AND GUYING EXISTING TREE	EA	25.000
	0580- 8- 31	LANDSCAPE- SHRUB, PRUNING/TRIMMING BED, 3 TO 6' AVERAGE HEIGHT	SY	1,000.000
	0580- 9- 1	LANDSCAPE- PALM, COMPLETE REMOVAL, LESS THAN 14' OF CLEAR TRUNK	EA	135.000
	0580- 9- 2	LANDSCAPE- PALM, COMPLETE REMOVAL, 14' AND GREATER OF CLEAR TRUNK	EA	94.000
	0580- 9- 3	LANDSCAPE- PALM, COMPLETE REMOVAL, PALM CLUMP	EA	154.000
	0580- 9- 10	LANDSCAPE- TREE, COMPLETE REMOVAL, 1" TO 8" DBH,	EA	215.000
	0580- 9- 11	LANDSCAPE- TREE, COMPLETE REMOVAL, 8 TO 24" DBH,	EA	82.000
	0580- 9- 12	LANDSCAPE- TREE, COMPLETE REMOVAL, 24" AND GREATER" DBH,	EA	78.000
	0580- 9- 30	LANDSCAPE- STUMP REMOVAL, LESS THAN 4"	EA	20.000
	0580- 9- 31	LANDSCAPE- STUMP REMOVAL, 4-24"	EA	8.000
	0580- 9- 32	LANDSCAPE- STUMP REMOVAL, 24-48"	EA	2.000
	0580- 9- 33	LANDSCAPE- STUMP REMOVAL, 48" OR GREATER	EA	2.000
	0580- 12- 30	LANDSCAPE- BONDED AGGREGATE TREE WELL SYSTEM	SY	500.000
	0580- 12- 31	PESTICIDE- FUNGICIDE	GA	5.000
	0580- 12- 32	PESTICIDE- INSECTICIDE	GA	5.000
	0580- 12- 33	ROOT BARRIER- 12"	LF	100.000
	0580- 12- 34	ROOT BARRIER- 20"	LF	100.000
	0580- 12- 35	ROOT BARRIER- 24"	LF	100.000
	0580- 12- 80	LANDSCAPE- FILL	CY	500.000
	0580- 12- 81	LANDSCAPE- EXCAVATION WITHOUT PLANTS	CY	500.000
	0580- 12- 82	MULCHING, 3" DEEP LAYER	SY	2,500.000
	0580- 12- 83	WEEDING- MANUAL	SY	2,000.000
	0580- 12- 84	HERBICIDE/CHEMICAL WEEDING	SY	4,000.000
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	100.000
	0581- 1- 8	RELOCATE TREES AND PALMS, >=14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	100.000
	0581- 1-271	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, <14.0' OF CLEAR TRUNK	EA	100.000
	0581- 1-272	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	100.000
	0581- 1-281	RELOCATE TREES AND PALMS, OTHER PALMS, 10.0"-18.0" DBH, <14.0' OF CLEAR TRUNK	EA	100.000
	0581- 1-282	RELOCATE TREES AND PALMS, OTHER PALMS, 10.0"-18.0" DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	50.000

**Call Order: 002 Proposal: E6P78**

ALT	Item	Description	Unit	Quantity
	0581- 1-291	RELOCATE TREES AND PALMS, OTHER PALMS, 18.1" OR GREATER DBH, <14.0' OF CLEAR TRUNK	EA	50.000
	0581- 1-292	RELOCATE TREES AND PALMS, OTHER PALMS, 18.1" OR GREATER DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	50.000
	0581- 1-300	RELOCATE TREES AND PALMS, TREE, LESS THAN OR EQUAL TO 3.0" DBH	EA	100.000
	0581- 1-310	RELOCATE TREES AND PALMS, TREE, 3.1" TO 4.0" DBH	EA	75.000
	0581- 1-320	RELOCATE TREES AND PALMS, TREE, 4.1" TO 6.0" DBH	EA	50.000
	0581- 1-330	RELOCATE TREES AND PALMS, TREE, 6.1" TO 8.0" DBH	EA	40.000
	0581- 1-340	RELOCATE TREES AND PALMS, TREE, 8.1" TO 14.0" DBH	EA	10.000
	0581- 1-350	RELOCATE TREES AND PALMS, TREE, 14.1" TO 16.0" DBH	EA	10.000
	0581- 1-360	RELOCATE TREES AND PALMS, TREE, 16.1" OR GREATER DBH	EA	5.000
	0581- 1-400	RELOCATE TREES AND PALMS, PALMS, MULTI-TRUNK OR CLUSTERING	EA	25.000
	0581- 1-500	RELOCATE TREES AND PALMS, TREES, MULTI-TRUNK OR CLUSTERING	EA	50.000
	0590- 2-109	IRRIGATION SYSTEM, 0-1.0" PVC WATER LINE	LF	900.000
	0590- 2-110	IRRIGATION SYSTEM, 1.1-2.0" PVC WATER LINE	LF	1,100.000
	0590- 2-111	IRRIGATION SYSTEM, 2.1-3.0" PVC WATER LINE	LF	300.000
	0590- 2-112	IRRIGATION SYSTEM, 3.1-4.0" PVC WATER LINE	LF	50.000
	0590- 3-101	IRRIGATION SYSTEM CONTROLLER, 1 STATION BATTERY OPERATED	EA	1.000
	0590- 3-102	IRRIGATION SYSTEM CONTROLLER, 2 STATION BATTERY OPERATED	EA	1.000
	0590- 3-103	IRRIGATION SYSTEM CONTROLLER, 4 STATION BATTERY OPERATED	EA	1.000
	0590- 3-104	IRRIGATION SYSTEM CONTROLLER, 6 STATION BATTERY OPERATED	EA	1.000
	0590- 3-105	IRRIGATION SYSTEM CONTROLLER, 12 STATION ELECTRIC OPERATED	EA	1.000
	0590- 3-106	IRRIGATION SYSTEM CONTROLLER, 24 STATION ELECTRIC OPERATED	EA	1.000
	0590- 4-106	IRRIGATION SYSTEM, 1.5" BACKFLOW PREVENTER	EA	1.000
	0590- 4-107	IRRIGATION SYSTEM, 2" BACKFLOW PREVENTER	EA	1.000
	0590- 5-109	IRRIGATION SYSTEM- 6" POP UP SPRINKLER HEAD	EA	100.000
	0590- 5-110	IRRIGATION SYSTEM- 12" POP UP SPRINKLER HEAD	EA	100.000
	0590- 5-111	IRRIGATION SYSTEM- 30-50' RADIUS ROTOR HEAD	EA	25.000
	0590- 5-112	IRRIGATION SYSTEM- OVER 50' RADIUS ROTOR HEAD	EA	25.000
	0590- 6-107	IRRIGATION SYSTEM CONTROLLER, RAIN SENSOR	EA	4.000
	0590- 6-113	IRRIGATION SYSTEM, 0-1.0" VALVE	EA	3.000
	0590- 6-114	IRRIGATION SYSTEM, 1.1-2.0" VALVE	EA	6.000
	0590- 6-116	IRRIGATION SYSTEM, 21"L x16" W x12"D VALVE BOX	EA	3.000
	0590- 6-117	IRRIGATION SYSTEM, IRRIGATION CONTROL WIRE	LF	800.000
	0591- 1-400	IRRIGATION SLEEVE, 4" DIAMETER	LF	300.000
	0591- 1-600	IRRIGATION SLEEVE, 6" DIAMETER	LF	100.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	06260129	Call Order: 003	Proposal: E6P84	District:06
Counties:	MIAMI-DADE			
Road Name:	TRAFFIC OPERATIONS PUSH-BUTTON ROADS MIAMI DADE COUNTY			
Limits:	Midpoint			
Project(s):	44626355201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	730	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of Miscellaneous Operations Push Button Roads in Miami-Dade County. Pre-qualification is required.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work

Award will be made at the Department Advertised Estimate Amount of \$1,000,000.00.

**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1- 1	MOBILIZATION- FOR WORK ORDER/PUSH BUTTON CONTRACTS (DO NOT BID) (44626355201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	300.000
	0102- 60-	WORK ZONE SIGN	ED	7,200.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	200.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	400.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,000.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,000.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,000.000
	0102-115-	TYPE III BARRICADE	ED	400.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	40.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	4.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,000.000
	0110- 21-	TREE PROTECTION BARRIER	LF	100.000

**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	700.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	700.000
	0160- 4-	TYPE B STABILIZATION	SY	4,000.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,500.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	500.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	500.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	200.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	1,000.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	1,000.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	5,000.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	2,000.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	500.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	500.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	200.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	600.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	600.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	300.000
	0425- 1-359	INLETS, CURB, TYPE P-5, MODIFY	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	50.000
	0425- 6-	VALVE BOXES, ADJUST	EA	50.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	200.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	100.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,000.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	500.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	10.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	600.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	250.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	100.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,500.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	500.000
	0527- 2-	DETECTABLE WARNINGS	SF	250.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,000.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	400.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	100.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	200.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,000.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.000



**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,200.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	500.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,000.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	20.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.000
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	300.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.000
<b>Section 0002 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	100.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	50.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	2.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	10.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	20.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	10.000
	0700- 1-312	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 12.0-20.0 SF	EA	10.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	8.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	50.000
	0700- 2-111	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	1.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	1.000

**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	40.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	10.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	5.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	1.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	1.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	20.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	15.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	25.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	20.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	2.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	4.000
	0700- 4-140	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT	EA	4.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	4.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	10.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	10.000
	0700-141-111	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	20.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	10.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	100.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	100.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	300.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	200.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,200.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	600.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,000.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.000

**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	50.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	50.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	30.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	250.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	2,000.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,500.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	1.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	10.000
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.000
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.000
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	1.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	1.000
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	2,000.000
<b>Section 0003 Lighting</b>				
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,000.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	400.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	400.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	4.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	2.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	4.000
	0715- 61-142	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 12' ARM LENGTH	EA	2.000

**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	2.000
	0715- 61-442	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 12' ARM LENGTH	EA	2.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	4.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	100.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	500.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	20.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	2,000.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0632- 7- 7	SIGNAL CABLE, REMOVE- OUTSIDE OF INTERSECTION	LF	1,000.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	50.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-113	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER NOT REQUIRED	AS	1.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	2.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	500.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	500.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	3.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000

**Call Order: 003 Proposal: E6P84**

ALT	Item	Description	Unit	Quantity
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0650- 1- 11	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	4.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	1.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	4.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	3.000
	0659- 1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	2.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	8.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	8.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	4.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	6.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-180	TRAFFIC CONTROLLER ASSEMBLY, F&I, CALTRANS W/STANDARD LOCK	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	4.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000



**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	06260129	Call Order: 004	Proposal: E6P99-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	RPM AND DELINEATOR INSTALLATION MIAMI-DADE COUNTY			
Limits:	Midpoint			
Project(s):	44424847201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

**Description:**

A contract for installing or replacing Raised Pavement Markers (RPMs) and flexible tubular delineators, on various Arterial State Roads in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific site is not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to accomplish, and the number of calendar days to complete the work.

The award will be made at the budgetary ceiling amount of \$300,000.00

**Call Order: 004 Proposal: E6P99-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 DELINEATORS (UN)</b>				
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	200.000
	0705- 11- 11	DELINEATOR POST, FURNISH & INSTALL ON EXISTING BASE	EA	50.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	50.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B) (On Concrete Curb)	EA	70,000.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	06260129	Call Order: 005	Proposal: E6Q02-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	CONCRETE CLEANING MIAMI-DADE COUNTY - ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	44429837201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		
Proposal Budget Estimate:	\$80,000.00			

Please read the full advertisement

**Description:**

A Contract for the removal of graffiti and stains from ground mounted and overhead signs, aluminum and metal surfaces, traffic control cabinets, light poles, sign panels, guardrails, and other surfaces. The work may also include poster removal from any structure, as well as cleaning and coating concrete surfaces such as sidewalks, bridges including beams and columns, concrete barrier walls, sound walls, concrete slopes, reinforced/retained earth wall faces and other concrete surfaces on various arterial state roads in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

\*\*\*The award will be made at the Department Advertised Estimate Amount of \$80,000.00.

**Call Order: 005 Proposal: E6Q02-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 GRAFFITI REMOVAL (SF)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	10.000
	0102- 60-	WORK ZONE SIGN	ED	400.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,250.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	25.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	25.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	800.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	100.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	25.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	35.000
	0104- 10- 3	SEDIMENT BARRIER	LF	50.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	50,055.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	205,007.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	10.000
	E563- 99-	GRAFFITI REMOVAL	SF	500.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	06260129	Call Order: 006	Proposal: E6Q09	District:06
Counties:	MIAMI-DADE			
Road Name:	STRIPING MIAMI-DADE COUNTY - ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	45785417201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	730	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

**Description:**

A Contract to apply new and refurbish thermoplastic traffic stripes and markings and remove existing thermoplastic traffic stripes and markings on various arterial state roads in Miami-Dade County. This contract includes applying new or refurbishing lane lines parallel to the direction of the traffic. The work excludes "Hot Spray". This contract is not renewable.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

\*\*\*The Award will be made at the Department Advertised Estimate Amount of \$400,000.00.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: E6Q09				
ALT	Item	Description	Unit	Quantity
<b>Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	40.000
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	1.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	1.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	1.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	1.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	1.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	2.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	75,000.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.200
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.200
	0713-103-122	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 8" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	1.000
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.000
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.200
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.000
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.000
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	10,000.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	70,000.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	30,000.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	40,000.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	10,005.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	06260129	Call Order: 007	Proposal: E6Q10-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	DRAINAGE CLEANING MIAMI-DADE COUNTY			
Limits:	Midpoint			
Project(s):	45789517201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

**Description:**

A Contract consisting of Drainage Cleaning on various Arterial State Roads in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of the Letting, the Engineer will issue a Work Document. This Work Document will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Department Advertised Estimate amount of \$300,000.00

**Call Order: 007 Proposal: E6Q10-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 CLEAN DRAINAGE STRUCTURES (LF)</b>				
	0102- 60-	WORK ZONE SIGN	ED	360.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	120.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E102- 74- 9	TRAFFIC CONES	ED	3,600.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	775.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	50.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	72,500.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	7,250.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	3,625.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	2,500.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	06260129	Call Order: 008	Proposal: E6Q11-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	CONCRETE INSTALLATION MIAMI-DADE COUNTY-ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	45790217201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

**Description:**

This contract consists of construction, reconstruction and removal of concrete sidewalks, driveways, curb cut ramps, curb & gutter, and special curb and gutter and traffic separator on various arterial state roads in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of the Letting, the Engineer will issue a Work Document. This Work Document will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Department Advertised Estimate amount of \$500,000.00

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Call Order: 008 Proposal: E6Q11-R0				
ALT	Item	Description	Unit	Quantity
<b>Section 0001 CONCRETE SIDEWALK REPAIR (SY)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	250.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.750
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	5,216.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	70.000
	0120- 6-	EMBANKMENT	CY	75.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	15.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	100.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	50.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F (Colored Concrete)	LF	25.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	25.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE (Colored Concrete)	LF	25.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	50.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	20.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	20.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4,100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK (Colored Concrete)	SY	400.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	400.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK (Colored Concrete)	SY	250.000
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	20.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	40.000
	E534- 72- 1	SOUND/NOISE BARRIER PANELS, F&I, REPLACE	SF	5.000
	E575- 1-	SODDING	SY	350.000

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	06260129	Call Order: 009	Proposal: E6Q14	District:06
Counties:	MIAMI-DADE			
Road Name:	DISTRICTWIDE BRIDGE MAINTENANCE IMPROVEMENTS - BRIDGE			
Limits:	87038000			
Project(s):	45794217201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.023 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.023 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$347,602.00

Please read the full advertisement

**Description:**

This Contract consists of performing maintenance repairs to Bridge No.870658 by removing existing asphalt, removing any loose grout from the existing shear keys, regrouting the shear keys between the slab units, restoring the existing asphalt pavement including the pavement markings, as well as replacing the nosing and expansion joints for the entire bridge in Miami Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each item to be bid. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific site is not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to accomplished, and the number of calendar days to complete the work.

Experience in Bridge Repair Form #850-070-04 must be submitted as an attachment with your electronic bid or your bid may be found non-responsive.

Award will be made at the Department Advertised Estimate Amount of \$347,602.00



**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Call Order: 009 Proposal: E6Q14				
ALT	Item	Description	Unit	Quantity
<b>Section 0001 BRIDGE DECK MAINTENANCE AND REPAIR (SF)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	256.000
	0102- 60-	WORK ZONE SIGN	ED	1,614.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,120.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	174.000
	0102-115-	TYPE III BARRICADE	ED	320.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	1,120.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	159.500
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	80.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	165.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	42.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	20.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.048
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.096
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.048