

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	06260129	Call Order: 009	Proposal: E6Q14	District:06
Counties:	MIAMI-DADE			
Road Name:	DISTRICTWIDE BRIDGE MAINTENANCE IMPROVEMENTS - BRIDGE			
Limits:	87038000			
Project(s):	45794217201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.023 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/26	
Total Proposal Length:	0.023 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$347,602.00

Please read the full advertisement

**Description:**

This Contract consists of performing maintenance repairs to Bridge No.870658 by removing existing asphalt, removing any loose grout from the existing shear keys, regrouting the shear keys between the slab units, restoring the existing asphalt pavement including the pavement markings, as well as replacing the nosing and expansion joints for the entire bridge in Miami Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each item to be bid. The Department's estimated quantities and the Contractors' bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific site is not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to accomplished, and the number of calendar days to complete the work.

Experience in Bridge Repair Form #850-070-04 must be submitted as an attachment with your electronic bid or your bid may be found non-responsive.

Award will be made at the Department Advertised Estimate Amount of \$347,602.00

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 009 Proposal: E6Q14**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 BRIDGE DECK MAINTENANCE AND REPAIR (SF)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	256.000
	0102- 60-	WORK ZONE SIGN	ED	1,614.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,120.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	174.000
	0102-115-	TYPE III BARRICADE	ED	320.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	1,120.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	159.500
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	80.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	165.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	42.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	20.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.048
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.096
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.048