

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 06260730      Call Order: 001      Proposal: E6Q13      District:06

Counties: MIAMI-DADE

Road Name: SR 907/ALTON RD FR N. OF 43RD ST TO N. OF ALLISON RD

Limits: 87037000

Project(s): 45602215201(\*)      Federal Aid No: N/A

Project(s): 45602215601      Federal Aid No: N/A

Total Roadway Length:	10.236 Miles	Contract Days:	250
Total Bridge Length:	0.047 Miles	Letting Date:	07/30/26
Total Proposal Length:	10.283 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$5,423,439.00

Please read the full advertisement

Description: A+B Bidding/Incentive-Disincentive

The improvements under this Contract consist of Resurfacing along SR 907/ Alton Road from N. of 43rd Street to N. of Allison Road in Miami-Dade County. Pre-qualification is required.

**NOTE: This is a cost plus time proposal(A+B). The following sites are cost plus time sites.**

Site	Description	Road Cost Per Day	Maximum Days
00	Contract Time	3000.00	250

**Call Order: 001 Proposal: E6Q13**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	880.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	100.000
	0458- 3- 1	GALVANIZED STEEL SIDEWALK COVER PLATE	LF	135.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (45602215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45602215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,670.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,830.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	250.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	514.000
	0107- 1-	LITTER REMOVAL	AC	109.990
	0107- 2-	MOWING	AC	51.880
	0110- 1- 1	CLEARING & GRUBBING (45602215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,206.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	21.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	98,695.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1.700
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	9,501.100
	0425- 5-	MANHOLE, ADJUST	EA	74.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,093.000

**Call Order: 001 Proposal: E6Q13**

ALT	Item	Description	Unit	Quantity
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	71.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	963.000
	0527- 2-	DETECTABLE WARNINGS	SF	660.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	227.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (45602215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45602215201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	84.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	19.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	8.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	39.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	13.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	100.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	37.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	9.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,111.000
	0706- 1-110	RAISED PAVEMENT MARKER, TYPE F INTERNALLY ILLUMINATED	EA	140.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45602215201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.053
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,925.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	8,094.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	840.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.340
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	48.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	124.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	526.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.384
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,658.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	134.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	7.367
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.018
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.133
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.797

**Call Order: 001 Proposal: E6Q13**

ALT	Item	Description	Unit	Quantity
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.133
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.066
<b>Section 0004 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	744.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	85.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	5.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	96.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0635- 2- 15	PULL & SPLICE BOX, F&I, 30" X 48" COVER SIZE	EA	1.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	5.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	5.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	436.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	430.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	5.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	17.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	8.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	13.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	9.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	9.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	30.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	10.000
<b>Section 0005 Utilities</b>				
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (45602215601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	59.000
	1080- 21-102	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 2"	EA	2.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	96.000