

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	06261119	Call Order: 004	Proposal: E6Q61-R0	District:06
Counties:	MIAMI-DADE			
Road Name:	ASPHALT REPAIR MIAMI-DADE COUNTY - ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	44603837201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	11/19/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		
Proposal Budget Estimate:	\$200,000.00			

Please read the full advertisement

Description:

The work under this Contract consists of providing labor, equipment and materials for repair of existing asphalt pavement on various arterial state roads in Miami-Dade County.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of the Letting, the Engineer will issue a Work Document. This Work Document will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Award will be made at the Department Advertised Estimate amount of \$200,000.00

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E6Q61-R0				
ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	150.000
	0102- 60-	WORK ZONE SIGN	ED	48.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	240.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	20.000
	0120- 1-	REGULAR EXCAVATION	CY	100.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	20.000
	0210- 2-	LIMEROCK-NEW MATERIAL FOR REWORKING BASE	CY	50.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	700.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,500.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	30.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	200.000
	0425- 1-611	INLETS, DITCH BOTTOM, TYPE K, <10'	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	100.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	10.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	50.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	3.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.100
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	2.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	120.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	1,800.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	450.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	150.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	20.000