

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	06261029	Call Order: 001	Proposal: E6P85	District:06
Counties:	MIAMI-DADE			
Road Name:	SR A1A/COLLINS AVENUE NB ON RAMP AND IVES DAIRY RD EB ON RAMP			
Limits:	87060000			
Project(s):	44974115201(*)	Federal Aid No: N/A		
Project(s):	45460715201	Federal Aid No: N/A		
Project(s):	45460815201	Federal Aid No: N/A		
Total Roadway Length:	0.089 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/26	
Total Proposal Length:	0.089 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120	
Proposal Budget Estimate:	\$808,984.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Overhead Signing along SR A1A/Collins Avenue Northbound on ramp SR 856 WB Overhead Sign 87S377, along Ives Dairy RD Eastbound at I-95 Southbound on Ramp Overhead Sign 87S698, and along SR A1A/Collins Ave NB 500Ft S/O SR-826 on Ramp Overhead Sign 87S376 in Miami-Dade County.

Prequalification is required.

Call Order: 001 Proposal: E6P85

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44974115201)	LS	1.000
	0101- 1-	MOBILIZATION (45460715201)	LS	1.000
	0101- 1-	MOBILIZATION (45460815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44974115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45460715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45460815201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	960.000
	0102- 60-	WORK ZONE SIGN	ED	2,580.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,400.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,920.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	230.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	438.000
	0102-115-	TYPE III BARRICADE	ED	370.000
	0110- 1- 1	CLEARING & GRUBBING (44974115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	8.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	9.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.800
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	8.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	62.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	62.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44974115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45460715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45460815201)	LS	1.000
Section 0002 Signing				
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	1.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-506	SIGN PANEL, RELOCATE, 101-200 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	1.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	1.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	1.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	2.000
	0700- 4-621	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, SPAN	EA	1.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	3.000
Section 0003 Landscape / Peripheral				
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (44974115201)	LS	1.000