

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 07181114 Call Order: 001 Proposal: E7M47-R0 District:07

Counties: DIST/ST-WIDE

Road Name: DISTRICTWIDE GROUND SUBSIDENCE REPAIR CONTRACT-VARIOUS ROADS

Limits: MAINT

Project(s): 41912715216(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	11/14/18
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

Work consists of Emergency roadway and ground repair in areas affected by sinkholes and/or water and storm related damage. This is a Districtwide contract and is of an emergency nature.

Contract will be awarded at the full budgetary amount of \$500,000.00, low bid will set the unit price.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

The previous contract number is E7M13-R0, let on 1/10/2018.

Call Order: 001 Proposal: E7M47-R0

ALT	Item	Description	Unit	Quantity
Section 0002 Roadway				
	0102- 60-	WORK ZONE SIGN	ED	1,000.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	50.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	50.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,000.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	200.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	50.000
	0102- 75- 2	TEMPORARY SEPARATOR, F&I REMAIN	LF	50.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	50.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	10.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	10.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	50.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	10.000
	0145- 71-	REINFORCEMENT GRID FOR SOIL STABILIZATION	SY	100.000

Call Order: 001 Proposal: E7M47-R0

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	50.000
	0173- 71-	DRILLING HOLES FOR PRESSURE GROUTING	EA	150.000
	0173- 76-	GROUT PIPE INSTALLATION	LF	4,200.000
	0173- 77- 3	SUBSURFACE PRESSURE GROUTING, CEMENT SLURRY	CY	400.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	75.000
	0287- 1-	ASPHALT TREATED PERMEABLE BASE	CY	10.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	200.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	200.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	200.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	200.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	200.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	200.000
	0327- 70- 10	MILLING EXIST ASPH PAVT, 5" AVG DEPTH	SY	200.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	200.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	200.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	20.000
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	20.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	20.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	20.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	20.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	20.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	20.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	20.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	20.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	10.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	10.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	10.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	50.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	200.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	30.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.250
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	100.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	100.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	100.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.250
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.250
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000

Call Order: 001 Proposal: E7M47-R0

ALT	Item	Description	Unit	Quantity
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	5.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	50.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.250
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.250
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	100.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.250
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.250
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	50.000
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"	GM	0.250
	0906-173- 17	SINGLE COMPONENT POLYURETHANE INJECTION, PROJECT 419127-1-52-16	GA	50.000
	0906-173- 18	TWO COMPONENT POLYURETHANE INJECTION, PROJECT 419127-1-52-16	LB	3,500.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E102- 1- 3	MAINTENANCE OF TRAFFIC (SITE SPECIFIC CONTRACTS)	LO	1.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	10.000
	E102- 20-	PORTABLE LIGHTING UNIT (MAST MOUNTED)	ED	5.000
	E102- 74- 9	TRAFFIC CONES	ED	500.000
	E102- 97- 1	TRUCK MOUNTED ATTENUATOR (TEMPORARY)	ED	1.000
	E710- 11-121	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	LF	100.000
	E710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	LF	100.000
	E710- 11-221	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	LF	100.000
	E710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	LF	100.000