

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 07180912      Call Order: 002      Proposal: E7M39-R0      District:07

Counties: CITRUS, HERNANDO, PASCO

Road Name: Storm water pipe rehabilitation - various roads

Limits: MAINT

Project(s): 41602637218(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	09/12/18
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$ 400,000.00

Please read the full advertisement

Description:

Work under this contract will consist of storm water pipe rehabilitation, replacement, desilting and video inspection.

Contract will be awarded at the full budgetary amount of \$400,000.00; low bid will set unit price.

Contractors must be prequalified in Drainage OR must complete and submit with their bid Form # 850-070-05 'Experience in Drainage Repair' showing that the Contractor or Project Superintendent has at least three (3) years of experience in the active performance of Drainage Repair work.

The previous contract number is E7L72-R0, let on 4/19/2017.

**Call Order: 002 Proposal: E7M39-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 BASE REPAIR (TN)</b>				
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	75.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	5.000
	0104- 10- 3	SEDIMENT BARRIER	LF	50.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	100.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	50.000
	0120- 5-	CHANNEL EXCAVATION	CY	10.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	15.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	100.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000
	0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	3.000
	0425- 4-	INLETS, ADJUST	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	5.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	5.000
	0425- 15- 51	INLET TOP, REPLACE, CURB INLET	EA	2.000
	0425- 78-	INLET CAP, PRECAST	EA	2.000
	0425- 82-	REPLACE GRATE	EA	4.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	10,000.000

**Call Order: 002 Proposal: E7M39-R0**

ALT	Item	Description	Unit	Quantity
	0430-94- 2	DESILTING PIPE, 25 - 36"	LF	5,000.000
	0430-94- 3	DESILTING PIPE, 37 - 48"	LF	1,500.000
	0430-94- 4	DESILTING PIPE, 49 - 60"	LF	1,500.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	32.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	80.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	80.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	32.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	32.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	8.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	8.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	8.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	8.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	8.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	8.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	50.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	25.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	50.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	25.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	25.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	5.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	5.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	1.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	1.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	1.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	100.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	4.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	4.000
	0431- 1- 1	PIPE LINER, OPTIONAL MATERIAL, 0-24"	LF	500.000
	0431- 1- 2	PIPE LINER, OPTIONAL MATERIAL, 25-36"	LF	500.000
	0431- 1- 3	PIPE LINER, OPTIONAL MATERIAL, 37-48"	LF	100.000
	0431- 1- 4	PIPE LINER, OPTIONAL MATERIAL, 49 - 60"	LF	50.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	100.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	50.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	25.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	50.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	32.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	200.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	10.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	10.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	50.000
	E430-949- 13	DESILTING PIPE (UNDERDRAIN) (4")	LF	500.000

**Call Order: 002 Proposal: E7M39-R0**

---

ALT	Item	Description	Unit	Quantity
	E430-949- 16	DESILTING PIPE (UNDERDRAIN) (6")	LF	500.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	18,000.000