

## **F9095 Questions and Answers #1**

1. Striping – Is the striping to be Paint or Thermoplastic – If it is Thermoplastic will the waiting period for Thermoplastic placement be enforced

**The striping will be standard paint.**

2. Landscaping – The plans state “ ALL REQUIRED LANDSCAPE AREAS AND BUFFER STRIPS SHALL BE PROVIDED WITH AN IRRIGATION SYSTEM TO ALLOW 100 PERCENT COVERAGE. ALL IRRIGATION LINES” Will Irrigation be required and if so where is a system that can be connected to

**The contractor is responsible for temporary irrigation until the plants are established. Muhly grass is a hardy, drought tolerant native species that will not require permanent irrigation after it is established. Temporary irrigation may be accomplished by water truck or other temporary means which do not necessarily require connection to a potable water main.**

3. Landscaping - The Plans State “PERFORM A SOIL TEST AND APPLY THE NECESSARY AMENDMENTS AND/OR FERTILIZER. THE PLANTING AREAS SHALL NOT BE UNSUITABLE COMPACTED BACKFILL, BUT FERTILE WELL-DRAINED LOAMY TOPSOIL WITH AN APPROPRIATE RATIO OF NITROGEN, POTASSIUM, PHOSPHORUS AND MICRO-NUTRIENTS (CORRESPONDING TO THE NEEDS OF A SOIL TEST)” Will This testing be required?

**The soil test is required to ensure the survival of the chosen planting material.**

4. Will any cross walk striping be required?

**No, the current cross walk striping is not affected by construction and no additional crosswalk length is required.**

5. Is the asphalt to be placed in one lift?

**The number and thickness of asphalt lifts are not dictated in the plans, but by standard specification 334.**