



Bid Questions and Answers Report

Date & Time:

4/25/2018 1:58:49 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4471  
Project: 434722-1-52-01  
Letting Date: 4/25/2018  
Localtion: CENTRAL OFFICE  
Description: SR 806 (ATLANTIC AVE)

---

Question: 21247: Pursuant to Bid Item #0700-8-136, FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL// UPS, FULL COLOR, 101-200 SF, please confirm the # of lines, # of characters per line, character height and pixel pitch. Regarding the pixel pitch, full color can be defined as either 33/34mm or 20mm, so clarifying the pixel pitch is critical to meeting the expectations of the End User. In review of the ADMS Cross Section, there was no clarification of the aforementioned criteria. Please confirm.

Posted: 2/27/2018 8:54:15 AM

---

Answer: Sign shall be capable of displaying  
2 lines with 11 characters per line using 18" character height and 3 lines with 16 characters per line using 12" character height  
Using Pixel pitch of 20mm

Status: ANSWER PUBLISHED

Posted: 3/5/2018 1:33:48 PM

---

Question: 21370: On page S-12, the cantilever structure at Sta. #304+75 lists (2) #700-3-207 Sign Panels, signifying an overhead sign panel from 201-300 sf in size. However, these signs on this sign structure are only 44 sf each. Based on this, should these (2) sign panels not be listed under 700-3-204 (Overhead Sign Panel 31-50 sf) instead? Please advise...

Posted: 3/7/2018 4:17:00 PM

---

Answer: The correct PI number should have been 700-3-204 with a quantity of 2. A plan revision will be provided before letting

Status: ANSWER PUBLISHED

Posted: 3/12/2018 4:42:26 PM