



Bid Questions and Answers Report

Date & Time:

8/29/2018 8:42:43 AM

District Address: District 7 Construction Office, located at 11201 N McKinley, Tampa, FL 33612

District Phone: (813) 975-6285

Proposal: T7418
Project: 436486-1-52-01
Letting Date: 8/29/2018
Location: CENTRAL OFFICE
Description: SR 586 (CURLEW RD)

Question: 23112: Pay Item Note 520-1 on Sheet No SQ-1 calls for asphalt base curb pad and additional curb thickness required to be included in the cost of the curb and gutter. Posted: 8/22/2018 10:34:45 AM

There is no detail in the plans showing the thickness of the curb pad or additional curb thickness

Also what curb pay items is this to be used for

Answer: The curb pad thickness is 5" and is to be paid under PIN 520-1-7. Please reference sheet 21, detail B, for the intended application. Status: ANSWER PUBLISHED
Posted: 8/24/2018 8:20:28 AM

Question: 23113: For ease of construction would the department consider changing the 1.5" Mill and 1.5" FC 12.5 to a 2" lift like the rest of the job. Posted: 8/22/2018 10:39:42 AM

Answer: Please bid per the pavement design shown in the contract plans. Status: ANSWER PUBLISHED
Posted: 8/24/2018 8:18:57 AM

Question: 23128: Please confirm that the lane closure on plan sheet 43; Temporary Traffic Control Plan (6), is to remain in place for the duration of the drainage work and is not subject to the temporary lane closure restriction hours on plan sheet 38 Temporary Traffic Control Plan (1). Posted: 8/22/2018 1:51:32 PM

Answer: The lane closure on plan sheet 43; Temporary Traffic Control Plan (6), is to remain in place for the duration of the proposed drainage work and is not subject to the temporary lane closure restriction hours shown on plan sheet 38. Status: ANSWER PUBLISHED
Posted: 8/24/2018 8:15:51 AM