



Bid Questions and Answers Report

Date & Time:

12/5/2018 9:04:22 AM

District Address: District 2 Construction Office, located at 1109 South Marion Avenue, Lake City, FL 32025

District Phone: (386) 961-7532

Proposal: T2709

Project: 212844-3-52-01

Letting Date: 12/5/2018

Localtion: CENTRAL OFFICE

Description: CR 361 (KEATON BEACH RD)

---

Question: 23954: Are Stay-In-Place forms allowed to be used for the Bridge Deck of this project (21284435201)?

Posted: 11/19/2018 11:36:26 AM

---

Answer: For the Cypress Creek Bridge (212844-3) stay in place metal forms can be used for the Bridge Deck based on the soil and water samples. For the Fish Creek Bridge (415248-1), it is a box culvert. If they plan to use cast in place, stay in place metal forms cannot be used because it is classified as extremely aggressive due to the presence of chlorides (salt water).

Status: ANSWER PUBLISHED

Posted: 11/30/2018 4:17:15 PM

---

Answer: Yes.

Status: ANSWER VOIDED

Posted: 11/30/2018 1:26:05 PM

---

Question: 23955: Regarding Dewatering, Sheet BW-03 Note 2 of the Culvert Package states, "Dewatering by normal pumping methods is not anticipated to be adequate..for the preparation/construction of foundation construction soils. All foundations are to be constructed in the DRY." The existing culvert site sits in a sandy tidal area that is prone to very high water as well.

Posted: 11/19/2018 11:49:01 AM

Because of these requirements and conditions, a coffer dam system will need to be used. Are there any restrictions on the use of a cofferdam system?

---

Answer: The Contractor has to adhere to the requirements of the permit conditions from SRWMD and ACOE. Please refer to Permits ACOE 20170728, and SRWMD 144536 located on the online ordering site.

Status: ANSWER PUBLISHED

Posted: 11/27/2018 10:52:47 AM