



Bid Questions and Answers Report

Date & Time:

1/31/2018 10:54:24 AM

District Address: District 1 Construction Office, located at 801 N Broadway, Bartow, FL 33830

District Phone: (863) 519-2222

Proposal: T1693

Project: 434502-1-52-01

Letting Date: 1/31/2018

Location: CENTRAL OFFICE

Description: EWELL RD

---

Question: 20666: Are plain neoprene bearing pads paid for under Item 400-148 or included in the cost of 450-8-33? Posted: 1/4/2018 5:37:08 PM

---

Answer: Plain neoprene bearing pads shall be paid for under pay Item 400-148. Status: ANSWER PUBLISHED  
Posted: 1/11/2018 1:21:13 PM

---

Question: 20745: DOES THE TEMPORARY SIGNALIZATION HAVE TO BE PORTABLE OR CAN IT BE TEMPORARY WITH WOOD POLES & STRAND Posted: 1/11/2018 1:59:22 PM

---

Answer: The contractor is to use portable signals as shown in the contract plans. Strain pole's system cannot be used because there is no location where you can place a temp signal pole that meets clear zone criteria and still maintain the minimum NEC and OSHA clearance for the OE while providing the required vertical clearance for the temporary signal heads over the travel lanes. Status: ANSWER PUBLISHED  
Posted: 1/16/2018 4:17:04 PM