

Call Order: 008 Proposal: T2700

ALT	Item	Description	Unit	Quantity
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	66.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	1,712.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,080.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	1,080.000
	0521- 6- 31	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, 27" HEIGHT	LF	632.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	31.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,660.700
	0530- 74-	BEDDING STONE	TN	591.400
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (41525015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (415250-1-52-01)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (415250-1-52-01)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,280.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	2,241.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	2,121.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,320.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	76.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	20.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	540.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,111.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	695.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	27.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (415250-1-52-01)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (415250-1-52-01)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (41525015201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.200
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,102.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	5,368.000
	0120- 4-	SUBSOIL EXCAVATION	CY	1,014.000
	0120- 6-	EMBANKMENT	CY	14,424.000
	0160- 4-	TYPE B STABILIZATION	SY	5,134.000
	0173- 79- 4	SOIL STABILIZATION/IMPROVEMENT BY COLUMN SUPPORTED EMBANKMENT, PROJECT 415250-1-52-01 (41525015201)	LS	1.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	4,396.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	330.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	389.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	387.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	1.400
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	6.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	3.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	2.000

Call Order: 008 Proposal: T2700

ALT	Item	Description	Unit	Quantity
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 1-881	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <10'	EA	10.000
	0425- 1-882	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, >10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	28.000
	0430-174-230	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 30"SD	LF	11.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	1,124.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	426.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	7.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,382.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	136.000
	0521- 72- 5	SHOULDER CONCRETE BARRIER WALL, RIGID-CURB & GUTTER	LF	1,149.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,086.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	235.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	48.000
	0527- 2-	DETECTABLE WARNINGS	SF	104.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	3,883.000
	0530- 74-	BEDDING STONE	TN	1,183.000
	0536- 73-	GUARDRAIL REMOVAL	LF	802.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	10,080.000
	0550- 10-222	FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	LF	945.000
	0550- 60-212	FENCE GATE, TYPE B, SINGLE, 6.1 - 12.0' OPENING	EA	2.000
	0570- 1- 1	PERFORMANCE TURF	SY	1,839.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,155.000
	0571- 1- 13	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 3	SY	1,436.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.786
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	448.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	211.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.062
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.055
	0916-438- 3	2ND GENERATION BAFFLE BOX, PROJECT 415250-1-52-01	EA	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	6.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41525015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	373.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	305.000

Call Order: 008 Proposal: T2700

ALT	Item	Description	Unit	Quantity
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	8.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	8.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.401
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.446
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.205
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.205
Section 0004 Utilities				
	1000- 5-	UTILITY WORK- JPA/UTILITY AGREEMENT, SEWER (41525015601)	LS	1.000
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (41525015604)	LS	1.000