

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180425 Call Order: 009 Proposal: T2701 District:02
 Counties: DUVAL
 Road Name: SR 9 (I-95)
 Limits: AT SR 102 (AIRPORT RD) AND ALONG 102 FROM DUVAL RD TO MAX LEGGETT PKWY
 Project(s): 20936525201(*) Federal Aid No: D217064B
 Project(s): 20936525601 Federal Aid No: N/A
 Total Roadway Length: 1.659 Miles Contract Days: 480
 Total Bridge Length: 0.000 Miles Letting Date: 04/25/18
 Total Proposal Length: 1.659 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days (Acq. time)
 Proposal Budget Estimate: \$9,672,111.00

Please read the full advertisement

Description:

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-17.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" folder before submitting your bid.

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutters, traffic signals, lighting, highway signing, guardrail, sidewalks/bicycle path, ITS, specialty retaining wall, utility work and other incidental construction on SR 9 (I-95) in Duval County at SR 102 (Airport Road) and along 102 from Duval Road to Max Leggett Parkway.

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20936525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20936525201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (20936525201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (20936525201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (20936525201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	152.000
	0102- 60-	WORK ZONE SIGN	ED	32,890.000
	0102- 61-	BUSINESS SIGN	EA	22.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	8,815.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	687.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	7,065.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	83.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	102,005.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	2,420.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	846.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	60.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,355.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	9.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	4,215.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,620.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,620.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	1,111.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	477.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	464.000
	0104- 9-	SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT	EA	2.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,323.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	66.000
	0107- 1-	LITTER REMOVAL	AC	228.130
	0107- 2-	MOWING	AC	190.190
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (20936525201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (20936525201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (20936525201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,777.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	8.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (20936525201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	19,469.000
	0120- 4-	SUBSOIL EXCAVATION	CY	128.000
	0120- 6-	EMBANKMENT	CY	6,964.000
	0160- 4-	TYPE B STABILIZATION	SY	24,211.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,623.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	453.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	14,248.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	1,672.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	929.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	39,313.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	800.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4,360.200
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	178.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22	TN	4,447.000
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76 -22	TN	422.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	20.100
	0350- 3- 13	PLAIN CEMENT CONCRETE PAVEMENT, 12"	SY	129.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	25.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	14.200
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	2.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	12.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	13.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	1.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0425- 1-511	INLETS, DT BOT, TYPE B, <10'	EA	3.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	4.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 1-891	INLETS, BARRIER WALL, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	9.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	6.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	129.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	63.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	112.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	2,048.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	534.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	235.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	432.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	8.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	5.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	6.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	162.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	4,916.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	7,126.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	133.000
	0520- 2- 8	CONCRETE CURB, TYPE RA	LF	179.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	965.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	97.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	162.000
	0521- 1-	MEDIAN CONCRETE BARRIER WALL	LF	197.000
	0521- 72- 5	SHOULDER CONCRETE BARRIER WALL, RIGID-CURB & GUTTER	LF	119.000
	0521- 72- 10	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 42"	LF	622.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,114.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	590.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	313.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	221.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	8.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	365.000
	0527- 2-	DETECTABLE WARNINGS	SF	983.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	172.000
	0536- 73-	GUARDRAIL REMOVAL	LF	454.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	2,112.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	32.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0570- 1- 1	PERFORMANCE TURF	SY	11,091.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	35,354.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.700
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.201
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	550.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	597.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	105.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.709
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.440
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	44.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	41.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.321
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	109.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20936525201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	65.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	38.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	5.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	7.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	2.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	17.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	5.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	2.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	1.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 4-126	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	3.000
	0700- 4-127	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	1.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	1.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	17.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	36.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	31.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	53.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20936525201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.630
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,460.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	929.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	760.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.147
	0711- 11-143	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE, 12" FOR ROUNDABOUT	GM	0.023
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	60.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	112.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	138.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	317.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.052
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	1,059.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,621.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	41.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	28.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	4.903
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.333
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.445
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.069
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.073
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	664.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	220.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	442.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0635- 3- 11	JUNCTION BOX, FURNISH & INSTALL, AERIAL	EA	6.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	666.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,802.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	6.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	8.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	22.000
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (20936525201)	LS	1.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,055.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,995.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	64.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	340.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	15.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	7.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	4.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	3.000
	0649- 21- 7	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-30'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	9.000
	0650- 1- 11	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	4.000
	0650- 1- 14	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	32.000
	0650- 1- 44	TRAFFIC SIGNAL, FURNISH & INSTALL PROGRAMMABLE, 3 SECTION, 1 WAY	AS	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	12.000
	0660- 1-111	LOOP DETECTOR INDUCTIVE, F&I, TYPE 11, 4 CH, SS, RM	EA	8.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	34.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	26.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	18.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	3.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	8.000
	0715- 5- 32	LUMINAIRE & BRACKET ARM- GALV STEEL, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	4.000
Section 0005 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20936525601)	LS	1.000
	1000- 5-	UTILITY WORK- JPA/UTILITY AGREEMENT, SEWER (20936525601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (20936525601)	LS	1.000
Section 0006 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,665.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,735.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,595.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	6,535.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	210.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	210.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	18.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	18.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	18.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	17.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	110.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	14.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	10.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	2,125.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 2-120	ALUMINUM POLE- INDEX 17900/695-001, FURNISH & INSTALL, 20'	EA	1.000
	0646- 2-600	ALUMINUM POLE- INDEX 17900/695-001, REMOVE	EA	1.000
	0676- 2-112	ITS CABINET, FURNISH & INSTALL, POLE MOUNT, 336S, 24" W X 46" H X 22" D	EA	5.000

Call Order: 009 Proposal: T2701

ALT	Item	Description	Unit	Quantity
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0682- 1-600	ITS CCTV CAMERA,, REMOVE & DISPOSAL	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	10.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	5.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	3.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 10-123	DMS SUPPORT STRUCTURE, CANTILEVER, 31-40 FT	EA	2.000
	0700- 10-124	DMS SUPPORT STRUCTURE, CANTILEVER, 41-50 FT	EA	1.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	1.000