

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180425 Call Order: 010 Proposal: T3661 District:03
 Counties: LEON
 Road Name: SR 63 (US 27)
 Limits: FROM N OF JOHN KNOX RD TO S OF SR 61 (THOMASVILLE RD)
 Project(s): 43255915201(*) Federal Aid No: D317054B
 Project(s): 43255915202 Federal Aid No: N/A
 Project(s): 43255915203 Federal Aid No: D317054B
 Project(s): 43255915204 Federal Aid No: N/A
 Total Roadway Length: 1.868 Miles Contract Days: 160
 Total Bridge Length: 0.000 Miles Letting Date: 04/25/18
 Total Proposal Length: 1.868 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 day Acquis.
 Proposal Budget Estimate: \$3,819,076.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing SR 63 from north of John Knox Road to south of SR 61 (Thomasville Road) in Leon County. Work under FPID 432559-1-52-01 includes milling/resurfacing, sidewalk upgrades, signalization work, signing and pavement markings, minor drainage improvements, ADA improvements to existing pedestrian features, and maintenance of traffic. Work under FPID 432559-1-52-02 includes adjustment of manholes for City of Tallahassee Electric. Work under FPID 432559-1-52-03 includes work at SR 61 including milling/resurfacing, minor widening, signalization, signing and pavement markings. Work under FPID 432559-1-52-04 includes adjustment of manholes and valves for City of Tallahassee Water, Sewer, and Gas.

Call Order: 010 Proposal: T3661

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43255915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43255915201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	96.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	364.000
	0102- 60-	WORK ZONE SIGN	ED	24,455.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871	ED	1,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	85,340.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	320.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	445.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,010.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,183.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	320.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,440.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,440.000
	0104- 10- 3	SEDIMENT BARRIER	LF	862.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	105.000
	0107- 1-	LITTER REMOVAL	AC	23.740

Call Order: 010 Proposal: T3661

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	5.380
	0110- 1- 1	CLEARING & GRUBBING (43255915201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,174.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	144.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43255915201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	58.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	341.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	58.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	294.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	76,384.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	5,301.400
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	5,255.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.200
	0425- 1-431	INLETS, CURB, TYPE J-3, <10'	EA	4.000
	0425- 1-441	INLETS, CURB, TYPE J-4, <10'	EA	2.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	4.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	4.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	5.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	4.000
	0425- 5-	MANHOLE, ADJUST	EA	30.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	73.000
	0425- 6-	VALVE BOXES, ADJUST	EA	129.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	148.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	15.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	146.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,672.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	104.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	76.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	29.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,714.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,444.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	1,770.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,105.000
	0530- 74-	BEDDING STONE	TN	4.500
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	341.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	3.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.798
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.256
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,568.000

Call Order: 010 Proposal: T3661

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	312.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,212.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.066
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.032
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.091
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	90.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.740
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	215.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.352
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.158
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255915202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255915203)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255915204)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	49.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	6.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	6.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	20.000
	0700- 1- 87	SINGLE POST SIGN, REPAIR- REPLACE POST, USE EXISTING SIGN PANEL	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	3.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	5.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	29.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43255915201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43255915203)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.348
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	614.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,289.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.091
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	93.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	348.000

Call Order: 010 Proposal: T3661

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.158
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	5,871.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,745.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	46.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	26.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.928
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.166
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.032
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.827
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.352
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	63.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,640.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	8.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	8.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	120.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	34.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	11.000
	0650- 1- 60	TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	20.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	20.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	26.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	55.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	79.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	60.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	40.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	10.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000